

APPENDIX H

ADA ACCESS SELF-EVALUATION

The following Self-Evaluation and Transition Plan were developed in accordance with the recommendations of Appendix G of the state's Open Space and Recreation Planner's Handbook (Executive Office of Energy and Environmental Affairs, Division of Conservation Services, rev. March 2008).

PART I: ADMINISTRATIVE REQUIREMENTS

1. **Designation of an ADA Coordinator:**

The ADA Coordinator for the Town of North Attleboro is the Building Commissioner, William McGrady (effective 9/26/23), see attached designation letter.

2. **Grievance Procedures**

See attached procedure for the general public to follow if filing a complaint alleging discrimination by the Town of North Attleborough.

3. **Public Notification Requirements**

The Town of North Attleborough does not discriminate on the basis of disability. Examples of notices and job postings are attached demonstrating compliance with Section 504 and ADA.

4. **Participation of Individuals with Disabilities or Organizations Representing the Disabled Community**

The North Attleborough Commission on Disability (COD) and ADA Coordinator were involved and contributed to the Self Evaluation, specifically the new Grievance Procedure. The town has completed a Facility Inventory and is committed to implementing the Transition Plan, below, with the involvement of persons with disabilities or an organization such as the COD. Also, staff at SRPEDD who are involved with access and ADA issues, assisted with preparation of the transition plan, below.

PART II: PROGRAM ACCESSIBILITY

Facility Inventory

Facility Inventory sheets, attached, were completed for actively used facilities under the jurisdiction of Park and Recreation and the Conservation Commission. The required upgrades to those facilities will be addressed through a 5-year Capital Improvement Plan utilizing capital and other municipal funds.

Transition Plan

Transition Plans have been developed for those facilities *requiring structural changes*. Implementation of the Transition Plan is the responsibility of the controlling commission or department. In some

instances, the town has management agreements in place with the state, therefore the planning, scheduling, and implementation of the transition plan will be conducted on a partnership basis. The below facility plans include the following information (1) physical obstacles, (2) description of necessary changes, (3) schedule for making those changes, and (4) the responsible party. These plans were developed in coordination with the North Attleboro ADA Coordinator.

APPLICABLE FACILITIES (CONSERVATION):

1. Facility Name:	WHITING’S POND BEACH AND BOAT RAMP
Description:	Swimming, boat launch (state boat ramp), fishing, parking.
Physical Obstacles:	Fishing area not accessible, no handrail
Required Changes:	Provide access mat and stable, firm surface for fishing area and handrail
Schedule:	Summer 2024-2025
Responsible Party:	Conservation Commission/Park and Recreation

2. Facility Name:	FALLS POND BEACH AND BOAT RAMP
Description:	Swimming, boat launch (state boat ramp), fishing, parking, family picnic area.
Physical Obstacles:	Ramp from parking lot to beach not fully accessible, no handrail. Fishing area has no handrail and is not stable surface
Required Changes:	Install handrail at ramp, fishing area Provide stable, firm surface for fishing area Add accessible picnic tables on firm, stable surface
Schedule:	Summer 2024-2025
Responsible Party:	Conservation Commission/Park and Recreation State Office of Fishing and Boating Access

3. Facility Name:	CHORNEY PROPERTY
Description:	86-acre open space area with trails, parking area and walking bridge spanning wetlands and stream.
Physical Obstacles:	Access route from trail head (parking area) to trail, trail width, surface, walking bridge- tread obstacles
Required Changes:	Comply with Guidelines as feasible, provide access route to trail, improve trail surface, address tread obstacle on walking bridge
Schedule:	2024-2027
Responsible Party:	Conservation Commission

No other Conservation properties currently require structural changes. Other properties under the control of the Commission listed in Section 5 and Appendix D do not have well established or maintained trail systems, parking, or buildings therefore it is not feasible to provide ADA accessibility at this time.

APPLICABLE FACILITIES (PARK & RECREATION)

1. Facility Name:	WORLD WAR I MEMORIAL PARK/ZOO
Description:	184-acre multi use property with ballfields, disc golf, petting zoo, playgrounds, hiking trails, picnic area, etc.
Physical Obstacles:	Access to warning signals
Required Changes:	Warning signal to be visual and audible
Schedule:	2024
Responsible Party:	Park Commission

2. Facility Name:	MASON FIELD HOUSE AND PLAYGROUND
Description:	Athletic fields, playground, Park Department Offices
Physical Obstacles:	Entrance vestibule, second floor access, stair nosings, bathrooms not accessible
Required Changes:	Improve entrance, replace stair nosings, bathroom improvements (sink, stall upgrades, grab bar, dispenser, floor surface, toilet)
Schedule:	2026-2028
Responsible Party:	Park Commission

3. Facility Name:	RUTH RHIND RECREATION AREA
Description:	Recreational area with ball fields, nature trails and picnic area
Physical Obstacles:	Trail surface, parking spaces
Required Changes:	Improve trail surface, provide accessible parking and signage
Schedule:	2025
Responsible Party:	Park Commission

4. Facility Name:	TOWN FOREST AND DOG PARK
Description:	85-acre wooded, upland property with new walking/hiking trails and new dog park
Physical Obstacles:	Picnic area, parking lot accessibility, protruding objects on trails
Required Changes:	New parking signage, picnic table clearance and stable, even ground surface under and around tables *walking trail improvements currently being made to provide full accessibility
Schedule:	2023-2027
Responsible Party:	Park Commission

5. Facility Name:	LESTAGE PROPERTY/CODDINGS SKATING POND
Description:	Old pasture converted to athletic fields, also has Coddling Skating Rink which is equipped with lights, 3 benches, and a walking trail.
Physical Obstacles:	Picnic area surface and table clearance
Required Changes:	Picnic table clearance and stable, even ground surface under and around tables
Schedule:	2025
Responsible Party:	Park Commission

Part III: Employment Practices

See attached statement from the ADA Coordinator attesting to the fact that the town's employment practices are in compliance with the Americans with Disabilities Act.

Michael D. Borg
Town Manager



TOWN OF NORTH ATTLEBOROUGH
43 South Washington Street
North Attleborough MA 02760
508-699-0100

September 28, 2023

Mr. William McGrady
43 South Washington Street
North Attleborough, MA 02760

RE: Reappointment as the Americans with Disabilities Act Coordinator

Dear Mr. McGrady,

Congratulations on your reappointment as the Americans with Disabilities Act (ADA) Coordinator for the Town of North Attleboro. At your earliest convenience please see the Town Clerk to be sworn in. Your term will expire on June 30, 2024.

Sincerely yours,

A handwritten signature in blue ink, appearing to read "Michael D. Borg", is written over the typed name.

Michael D. Borg
Town Manager

CC: Town Clerk Pat McNielly

MICHAEL D. BORG
Town Manager



TOWN OF NORTH ATTLEBOROUGH
43 South Washington Street
North Attleborough, MA 02760

September 28, 2023

MEMORANDUM FOR RECORD

SUBJECT: Policy Letter 014- Equal Access to Public Facilities and Activities

1. **Scope.** The following grievance policy is established to meet the requirements of the Americans with Disabilities Act (ADA). It should be used by any individual who wishes to file a complaint alleging discrimination on the basis of disability in employment practices and policies or the provision of programs, meetings, services, and benefits by the Town of North Attleborough.

2. **Complaint Procedures.**

a. A grievance may be submitted in written form or verbally to the Town of North Attleboro ADA Coordinator. Assistance in writing the grievance will be available to all individuals. The grievance should contain as much information as possible about the alleged discrimination (name, address, phone number, location, and description of problem, etc.). Other arrangements for submission of a grievance such as a personal interview or tape recording will be made available for the visually impaired or those with motor impairments.

b. All complaints should be submitted promptly by the grievant but no later than **60 calendar days** of the alleged violation to:

William McGrady, ADA Coordinator
43 South Washington Street
North Attleborough, MA 02760
508-699-0100 wmcgrady@nattleboro.com

3. **Complaint Investigation.**

a. Within **15 calendar days** of receipt of the complaint, the ADA Coordinator will meet with the grievant to discuss the complaint and possible resolutions. After investigating, the Coordinator will respond in writing (or a format sensitive to the needs of the grievant). The response will explain the position of the Town of North Attleborough and offer options for substantive resolution of the complaint.

b. If the response by the ADA Coordinator does not satisfactorily resolve the issue, the grievant and/or his or her designee may appeal the decision in writing within **15 calendar days**

after receipt of the response to the Town Manager. Assistance in writing the appeal will be available to all individuals.

c. Within 30 calendar days after the receipt of the appeal, the Town Manager will meet with the ADA Coordinator and grievant to discuss the matter. The Town Manager will issue a decision in writing (or a format sensitive to the needs of the grievant) with a final resolution of the issue.

d. All complaints received by the ADA Coordinator and responses from the Town Manager will be kept by the Town of North Attleborough for a period of three years. These documents may be requested by the appropriate federal agency should an investigation into alleged discrimination on the basis of disability status be initiated.

4. **Corrective Action.** If it is determined that equal access has not been provided to public facilities or activities or discrimination has occurred on the basis of disability, the Town will act promptly to take corrective action as appropriate under the circumstances.

5. Point of Contact for this policy letter is the undersigned at mborg@nattleboro.com or 508-699-0100.

MICHAEL D. BORG
Town Manager
North Attleborough, Massachusetts



Town of North Attleborough
Human Resources Department
North Attleborough Public Schools & Town Government

Catherine M. Calicchia
Director of Human Resources

Phone: (508) 643-2175
Fax: (508) 643-2144

JOB POSTING
TOWN GOVERNMENT

POSITION TITLE: **PUBLIC SAFETY DISPATCHER**
POLICE DEPARTMENT
FULL-TIME (NIGHT SHIFT)
PAY: \$23.65 – \$30.95 per hour

Technical and administrative work dispatching and monitoring the communications center located at the Police Department for both Police and Fire Service. Monitors all town alarm systems and answers emergency 911 calls. Previous experience in dispatching and/or E-911 preferred.

The successful candidate(s) will undergo a 40 hour Basic Public Safety Telecommunication Course along with a two-day 911 training course. Applicants who have a CJIS certification, EMD and CPR certification are preferred

Salary/Benefits as per the MASSCOP PUBLIC SAFETY DISPATCHERS Local 436 Collective Bargaining Agreement

POSTING DATE: AUGUST 15, 2022

APPLICATION DEADLINE: AUGUST 26, 2022

APPLICATION PROCEDURE: **Submit cover letter and resume to:**
hrstaff@nattleboro.com

EXPERIENCE

Begin with your present / last job. You may complete this section or attach a resume to this form.

EMPLOYER _____ TELEPHONE _____

DATES EMPLOYED _____

ADDRESS _____ JOB TITLE _____

DUTIES PERFORMED _____

SUPERVISOR _____ REASON FOR LEAVING _____

EMPLOYER _____ TELEPHONE _____

DATES EMPLOYED _____

ADDRESS _____ JOB TITLE _____

DUTIES PERFORMED _____

SUPERVISOR _____ REASON FOR LEAVING _____

EMPLOYER _____ TELEPHONE _____

DATES EMPLOYED _____ JOB TITLE _____

ADDRESS _____

DUTIES PERFORMED _____

SUPERVISOR _____ REASON FOR LEAVING _____

EMPLOYER _____ DATES EMPLOYED _____

ADDRESS _____ JOB TITLE _____

DUTIES PERFORMED _____

SUPERVISOR _____ REASON FOR LEAVING _____

REFERENCES

Provide information for three work-related references:

NAME _____ **TITLE** _____

ADDRESS _____ **TEL #** _____

RELATIONSHIP _____

NAME _____ **TITLE** _____

ADDRESS _____ **TEL #** _____

RELATIONSHIP _____

NAME _____ **TITLE** _____

ADDRESS _____ **TEL #** _____

RELATIONSHIP _____

EDUCATION

	Name / Location	Course of Study	Years Completed/ Current Year	Did you Graduate?	Degree Pursuing/ed
Example	Framingham State University - Framingham, MA	Elementary Education	3 - Senior Year	<input type="radio"/> YES <input checked="" type="radio"/> NO	Bachelor's
High School				<input type="radio"/> YES <input type="radio"/> NO	
College				<input type="radio"/> YES <input type="radio"/> NO	
Other				<input type="radio"/> YES <input type="radio"/> NO	

SPECIAL SKILLS AND QUALIFICATIONS

Please describe any special training, experience, or job related skills that you have that will help us evaluate your application for employment. Include special skills, machines operated, licenses, professional affiliations, honors and awards, publications, etc.

CERTIFICATION AND RELEASE

- I certify that answers given herein are true and complete to the best of my knowledge. I understand that any false or misleading information given in my application or interview, including any omission, may result in disqualification for employment or discharge at any time during employment.
- I authorize investigation of all statements contained in this application for employment as may be necessary in arriving at an employment decision.
- I understand that any offer of employment may be contingent upon the successful result of a medical exam, employment references, education, professional certifications and/or licenses, driver's license (if required for the job), and/or background check.
- In the event of employment, I understand that I am required to abide by all rules and regulations of the Town of North Attleborough and/or North Attleborough Public Schools.

SIGNATURE

DATE

While the Town of North Attleborough/North Attleborough Public Schools does not require or request applicants or employees to take a lie detector test, state law requires the following notice:

“It is unlawful in Massachusetts to require or administer a lie detector test as a condition of employment. An employer who violates this law shall be subject to criminal penalties and civil liability”

Antonio J. Morabito III
Assistant Town Manager



TOWN OF NORTH ATTLEBOROUGH
43 South Washington Street
North Attleborough MA 02760
508-699-0100

February 9, 2023

Melissa Cryan
Executive Office of Energy and Environmental Affairs
Division of Conservation Services
100 Cambridge Street
Boston, MA 02114

RE: TOWN OF NORTH ATTLEBOROUGH- ADA COMPLIANCE


Dear Ms. Cryan,

As the town's ADA Coordinator, I am pleased to submit the following statement in accordance with the ADA Access Self Evaluation requirements of the Open Space and Recreation Plan.

The Town of North Attleborough's employment practices are in compliance with the Americans with Disabilities Act. These practices include the following major categories: Recruitment, Personnel Actions, Leave Administration, Training, Tests, Medical Exams/Questionnaires, Social and Recreational Programs, Fringe Benefits, Collective Bargaining Agreements and Wage and Salary Administration. All of these activities are conducted within the requirements of the ADA Guidelines.

If you need any further information, please let me know.

Respectfully,


Antonio J. Morabito III
Interim ADA Coordinator

ADA FACILITY INVENTORY

LOCATION: *Whiting's Pond Beach + Boat Ramp*

ACTIVITY	EQUIPMENT	NOTES
Picnic Facilities	Tables & Benches <i>N/A</i>	<input type="checkbox"/> Located adjacent to accessible paths
		<input type="checkbox"/> Access to Open Spaces
		<input type="checkbox"/> Back and Arm Rests
		<input type="checkbox"/> Adequate number
	Grills <i>N/A</i>	<input type="checkbox"/> Height of Cooking Surface
		<input type="checkbox"/> Located adjacent to accessible paths
	Trash Cans	<input checked="" type="checkbox"/> Located adjacent to accessible paths
<i>N/A</i> Picnic Shelters	<input type="checkbox"/> Located adjacent to accessible paths	
	<input type="checkbox"/> Located near accessible infrastructure and amenities	
Trails	<i>N/A</i>	<input type="checkbox"/> Surface material
		<input type="checkbox"/> Dimensions
		<input type="checkbox"/> Rails
		<input type="checkbox"/> Accessible signage
Swimming Facilities	Pools <i>N/A</i>	<input type="checkbox"/> Entrance
		<input type="checkbox"/> Location from accessible parking
		<input type="checkbox"/> Safety features
	Beaches	<input checked="" type="checkbox"/> Location from accessible path into water
		<input type="checkbox"/> Handrails
		<input checked="" type="checkbox"/> Location from accessible parking
		<input checked="" type="checkbox"/> Shade provided
Play Areas	Play Equipment <i>N/A</i>	<input type="checkbox"/> Same experience provided to all
	<i>N/A</i> Access Routes	<input type="checkbox"/> Located adjacent to accessible paths
		<input type="checkbox"/> Enough space between equipment for wheelchair
Game Areas	<i>N/A</i> Access Routes	<input type="checkbox"/> Located adjacent to accessible paths
		<input type="checkbox"/> Berm cuts onto courts
	<i>N/A</i> Equipment	<input type="checkbox"/> Height
		<input type="checkbox"/> Dimensions
		<input type="checkbox"/> Spectator Seating

Boat Docks	N/A Access Routes	<input type="checkbox"/> Located adjacent to accessible paths
		<input type="checkbox"/> Handrails
Fishing Facilities <i>A</i>	Access Routes	<input type="checkbox"/> Located adjacent to accessible paths <i>NO</i>
		<input type="checkbox"/> Handrails <i>NO</i>
	Equipment <i>N/A</i>	<input type="checkbox"/> Arm Rests
		<input type="checkbox"/> Bait Shelves
		<input type="checkbox"/> Fish Cleaning Tables
Programming	<input checked="" type="checkbox"/> Learn-to-Swim <i>offered</i>	
	<input type="checkbox"/> Guided Hikes	
	<input type="checkbox"/> Interpretive Programs	
Services	<input checked="" type="checkbox"/> Information available in alternative formats <i>website</i>	
	<input checked="" type="checkbox"/> Process to request interpretive services <i>website</i>	

PARKING			
TOTAL SPACES		REQUIRED ACCESSIBLE SPACES	
Up to 25	<input checked="" type="checkbox"/>	1 space	
26-50	<input type="checkbox"/>	2 spaces	
51-75	<input type="checkbox"/>	3 spaces	
76-100	<input type="checkbox"/>	4 spaces	
101-150	<input type="checkbox"/>	5 spaces	
151-200	<input type="checkbox"/>	6 spaces	
201-300	<input type="checkbox"/>	7 spaces	
301-400	<input type="checkbox"/>	8 spaces	
401-500	<input type="checkbox"/>	9 spaces	
ACCESSIBLE SPACE SPECIFICATIONS	YES	NO	COMMENTS/TRANSITION NOTES
Accessible space located closest to accessible entrance	<input type="checkbox"/>	<input type="checkbox"/>	<i>need accessible entrance</i>
Where spaces cannot be located within 200 ft of accessible entrance, drop-off area is provided within 100 ft.	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Minimum width of 13 ft includes 8 ft space plus 5 ft access aisle	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Van space – minimum of 1 van space for every accessible space, 8 ft wide plus 8 ft aisle. Alternative is to make all accessible spaces 11 ft wide with 5 ft aisle.	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Sign with international symbol of accessibility at each space or pair of spaces	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Sign minimum 5 ft, maximum 8 ft to top of sign	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Surface evenly paved or hard-packed (no cracks)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Surface slope less than 1:20, 5%	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Curbcut to pathway from parking lot at each space or pair of spaces, if sidewalk (curb) is present	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Curbcut is a minimum width of 3 ft, excluding sloped sides, has sloped sides, all slopes not to exceed 1:12, and textured or painted yellow	<input type="checkbox"/>	<input checked="" type="checkbox"/>	

RAMPS <i>No ramp</i>			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Slope Maximum 1:12	<input type="checkbox"/>	<input type="checkbox"/>	
Minimum width 4 ft between handrails	<input type="checkbox"/>	<input type="checkbox"/>	
Handrails on both sides if ramp is longer than 6 ft	<input type="checkbox"/>	<input type="checkbox"/>	
Handrails at 34" and 19" from ramp surface	<input type="checkbox"/>	<input type="checkbox"/>	
Handrails extend 12" beyond top and bottom	<input type="checkbox"/>	<input type="checkbox"/>	
Handgrip oval or round	<input type="checkbox"/>	<input type="checkbox"/>	
Handgrip smooth surface	<input type="checkbox"/>	<input type="checkbox"/>	
Handgrip diameter between 1½" and 2"	<input type="checkbox"/>	<input type="checkbox"/>	
Clearance of 1½" between wall and wall rail	<input type="checkbox"/>	<input type="checkbox"/>	
Non-slip surface	<input type="checkbox"/>	<input type="checkbox"/>	
Level platforms (4ft x 4 ft) at every 30 ft, at top, at bottom, at change of direction	<input type="checkbox"/>	<input type="checkbox"/>	

SITE ACCESS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Accessible path of travel from passenger disembarking area and parking area to accessible entrance	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<i>Flat surface but no accessibility through sand from parking area</i>
Disembarking area at accessible entrance	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<i>no accessible entrance</i>
Surface evenly paved or hard-packed	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<i>sand only</i>
No ponding of water	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

PATH OF TRAVEL			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Path does not require the use of stairs	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Path is stable, firm and slip resistant	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<i>need path of travel to beach/water</i>
3 ft wide minimum	<input type="checkbox"/>	<input type="checkbox"/>	
Slope maximum 1:20 (5%) and maximum cross pitch is 2% (1:50).	<input type="checkbox"/>	<input type="checkbox"/>	
Continuous common surface, no changes in level greater than ½ inch	<input type="checkbox"/>	<input type="checkbox"/>	
Any objects protruding onto the pathway must be detected by a person with a visual disability using a cane	<input type="checkbox"/>	<input type="checkbox"/>	

PATH OF TRAVEL			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Objects protruding more than 4" from the wall must be within 27" of the ground, or higher than 80"	<input type="checkbox"/>	<input type="checkbox"/>	
Curb on the pathway must have curb cuts at drives, parking and drop-offs	<input type="checkbox"/>	<input type="checkbox"/>	

ENTRANCES <i>MMA No Internal Facilities</i>			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Primary public entrances accessible to person using wheelchair, must be signed, gotten to independently, and <i>not</i> be the service entrance	<input type="checkbox"/>	<input type="checkbox"/>	
Level space extending 5 ft. from the door, interior and exterior of entrance doors	<input type="checkbox"/>	<input type="checkbox"/>	
Minimum 32" clear width opening (i.e. 36" door with standard hinge)	<input type="checkbox"/>	<input type="checkbox"/>	
At least 18" clear floor area on latch, pull side of door	<input type="checkbox"/>	<input type="checkbox"/>	
Door handle no higher than 48" and operable with a closed fist	<input type="checkbox"/>	<input type="checkbox"/>	
Vestibule is 4 ft plus the width of the door swinging into the space	<input type="checkbox"/>	<input type="checkbox"/>	
Entrance(s) on a level that makes elevators accessible	<input type="checkbox"/>	<input type="checkbox"/>	
Door mats less than ½" thick are securely fastened	<input type="checkbox"/>	<input type="checkbox"/>	
Door mats more than ½" thick are recessed	<input type="checkbox"/>	<input type="checkbox"/>	
Grates in path of travel have openings of ½" maximum	<input type="checkbox"/>	<input type="checkbox"/>	
Signs at non-accessible entrance(s) indicate direction to accessible entrance	<input type="checkbox"/>	<input type="checkbox"/>	
Emergency egress – alarms with flashing lights and audible signals, sufficiently lighted	<input type="checkbox"/>	<input type="checkbox"/>	

STAIRS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
No open risers	<input type="checkbox"/>	<input type="checkbox"/>	
Nosings not projecting	<input type="checkbox"/>	<input type="checkbox"/>	
Treads no less than 11" wide	<input type="checkbox"/>	<input type="checkbox"/>	
Handrails on both sides	<input type="checkbox"/>	<input type="checkbox"/>	
Handrails 34"-38" above tread	<input type="checkbox"/>	<input type="checkbox"/>	
Handrail extends a minimum of 1 ft beyond top and bottom riser (if no safety hazard and space permits)	<input type="checkbox"/>	<input type="checkbox"/>	
Handgrip oval or round	<input type="checkbox"/>	<input type="checkbox"/>	
Handgrip has a smooth surface	<input type="checkbox"/>	<input type="checkbox"/>	
Handgrip diameter between 1¼" and 1½"	<input type="checkbox"/>	<input type="checkbox"/>	
1½" clearance between wall and handrail	<input type="checkbox"/>	<input type="checkbox"/>	

DOORS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Minimum 32" clear opening	<input type="checkbox"/>	<input type="checkbox"/>	
At least 18" clear floor space on pull side of door	<input type="checkbox"/>	<input type="checkbox"/>	
Closing speed minimum 3 seconds to within 3" of the latch	<input type="checkbox"/>	<input type="checkbox"/>	
Maximum pressure 5 pounds interior doors	<input type="checkbox"/>	<input type="checkbox"/>	
Threshold maximum ½" high, beveled on both sides	<input type="checkbox"/>	<input type="checkbox"/>	
Hardware operable with a closed fist (no conventional doorknobs or thumb latch devices)	<input type="checkbox"/>	<input type="checkbox"/>	
Hardware minimum 36", maximum 48" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
Clear, level floor space extends out 5 ft from both sides of the door	<input type="checkbox"/>	<input type="checkbox"/>	
Door adjacent to revolving door is accessible and unlocked	<input type="checkbox"/>	<input type="checkbox"/>	
Doors opening into hazardous area have hardware that is knurled or roughened	<input type="checkbox"/>	<input type="checkbox"/>	

RESTROOMS <i>Portable accessible bathroom</i>			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
5 ft turning space measured 12" from the floor	<input type="checkbox"/>	<input type="checkbox"/>	
AT LEAST ONE SINK			
SPECIFICATION <i>N/A</i>	YES	NO	COMMENTS/TRANSITION NOTES
Clear floor space of 30" by 48" to allow a forward approach	<input type="checkbox"/>	<input type="checkbox"/>	
Mounted without pedestal or legs, height 34" to top of rim	<input type="checkbox"/>	<input type="checkbox"/>	
Extends at least 22" from the wall	<input type="checkbox"/>	<input type="checkbox"/>	
Open knee space a minimum 19" deep, 30" width, and 27" high	<input type="checkbox"/>	<input type="checkbox"/>	
Cover exposed pipes with insulation	<input type="checkbox"/>	<input type="checkbox"/>	
Faucets operable with closed fist (lever or spring activated handle)	<input type="checkbox"/>	<input type="checkbox"/>	
AT LEAST ONE STALL			
SPECIFICATION <i>N/A</i>	YES	NO	COMMENTS/TRANSITION NOTES
Accessible to person using wheelchair at 60" wide by 72" deep	<input type="checkbox"/>	<input type="checkbox"/>	
Stall door is 36" wide	<input type="checkbox"/>	<input type="checkbox"/>	
Stall door swings out	<input type="checkbox"/>	<input type="checkbox"/>	
Stall door is self closing	<input type="checkbox"/>	<input type="checkbox"/>	
Stall door has a pull latch	<input type="checkbox"/>	<input type="checkbox"/>	
Lock on stall door is operable with a closed fist, and 32" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
Coat hook is 54" high	<input type="checkbox"/>	<input type="checkbox"/>	
TOILET <i>N/A</i>			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
18" from center to nearest side wall	<input type="checkbox"/>	<input type="checkbox"/>	
42" minimum clear space from center to farthest wall or fixture	<input type="checkbox"/>	<input type="checkbox"/>	
Top of seat 17"-19" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
GRAB BARS <i>N/A</i>			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
On back and side wall closest to toilet	<input type="checkbox"/>	<input type="checkbox"/>	
1 1/4" diameter	<input type="checkbox"/>	<input type="checkbox"/>	
1 1/2" clearance to wall	<input type="checkbox"/>	<input type="checkbox"/>	
Located 30" above and parallel to the floor	<input type="checkbox"/>	<input type="checkbox"/>	
Acid-etched or roughened grab bar surface	<input type="checkbox"/>	<input type="checkbox"/>	
42" long grab bars	<input type="checkbox"/>	<input type="checkbox"/>	

RESTROOMS <i>Accessible porta-john</i>			
FIXTURES			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Toilet paper dispenser is 24" above floor	<input type="checkbox"/>	<input type="checkbox"/>	
One mirror set a maximum 38" to bottom (if tilted, 42")	<input type="checkbox"/>	<input type="checkbox"/>	
Dispensers (towel, soap, etc.) at least one of each a maximum 42" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	

FLOORS <i>MA</i>			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Non-slip surface	<input type="checkbox"/>	<input type="checkbox"/>	
Carpeting is high-density, low pile, non-absorbent, stretched taut, securely anchored	<input type="checkbox"/>	<input type="checkbox"/>	
Corridor width minimum is 3 ft	<input type="checkbox"/>	<input type="checkbox"/>	
Objects (signs, ceiling lights, fixtures) can only protrude 4" into the path of travel from a height of 27" to 80" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	

DRINKING FOUNTAINS <i>N/A</i>			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Spouts no higher than 36" from floor to outlet	<input type="checkbox"/>	<input type="checkbox"/>	
Hand operated push button or level controls	<input type="checkbox"/>	<input type="checkbox"/>	
Spouts located near front with stream of water as parallel to front as possible	<input type="checkbox"/>	<input type="checkbox"/>	
If recessed, recess a minimum 30" width, and no deeper than depth of fountain	<input type="checkbox"/>	<input type="checkbox"/>	
If no clear knee space underneath, clear floor space 30" x 48" to allow parallel approach	<input type="checkbox"/>	<input type="checkbox"/>	

TELEPHONES <i>N/A</i>			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Highest operating part a maximum 54" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
Access within 12" of phone, 30" high by 30" wide	<input type="checkbox"/>	<input type="checkbox"/>	
Adjustable volume control on headset so identified	<input type="checkbox"/>	<input type="checkbox"/>	

SIGNALS, OUTLETS, AND SWITCHES <i>N/A</i>			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Switches and controls for light, heat, ventilation, windows, fire alarms, thermostats, etc., must be a minimum of 36" and a maximum of 48" above the floor for a forward reach, a maximum of 54" for a side reach	<input type="checkbox"/>	<input type="checkbox"/>	
Electrical outlets centered no lower than 18" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
Warning signals must be visual as well as audible	<input type="checkbox"/>	<input type="checkbox"/>	

SIGNS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Mounting height must be 60" to centerline of the sign	<input type="checkbox"/>	<input type="checkbox"/>	<i>N/A</i>
Within 18" of door jamb or recessed	<input type="checkbox"/>	<input type="checkbox"/>	<i>N/A</i>
Letters and numbers at least 1/4" high	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Letters and numbers raised .03"	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Letters and numbers contrast with the background color	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

SWIMMING POOLS <i>N/A</i>			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Ramp at least 34" wide with a non-slip surface extending into the shallow end, slope not exceeding 1:6 with handrails on both sides	<input type="checkbox"/>	<input type="checkbox"/>	<i>Note: Pools may accommodate either ramp or lifting access.</i>
Lifting device	<input type="checkbox"/>	<input type="checkbox"/>	<i>Note: Pools may accommodate either ramp or lifting access.</i>
Transfer area 18" above the path of travel and a minimum of 18" wide	<input type="checkbox"/>	<input type="checkbox"/>	
Unobstructed path of travel not less than 48" wide around pool	<input type="checkbox"/>	<input type="checkbox"/>	
Non-slip surface	<input type="checkbox"/>	<input type="checkbox"/>	

SHOWER ROOMS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Stalls 36" by 60" minimum, with a 36" door opening	<input type="checkbox"/>	<input type="checkbox"/>	<i>Note: Showers must accommodate both wheel-in and transfer use</i>
Floors are pitched to drain the stall at the corner farthest from entrance	<input type="checkbox"/>	<input type="checkbox"/>	
Floors are non-slip surface	<input type="checkbox"/>	<input type="checkbox"/>	
Controls operate by a single lever with a pressure balance mixing valve	<input type="checkbox"/>	<input type="checkbox"/>	

Controls are located on the center wall adjacent to the hinged seat	<input type="checkbox"/>	<input type="checkbox"/>	
Shower heads attached to a flexible metal hose	<input type="checkbox"/>	<input type="checkbox"/>	
Shower heads attached to wall mounting adjustable from 42" to 72" above the floor	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Seat is hinged and padded and at least 16" deep, folds upward, securely attached to side wall, height is 18" to the top of the seat, and at least 24" long	<input type="checkbox"/>	<input type="checkbox"/>	
Soap trays without handhold features unless they can support 250 pounds	<input type="checkbox"/>	<input type="checkbox"/>	
2 grab bars are provided, one 30" and one 48" long, or one continuous L shaped bar	<input type="checkbox"/>	<input type="checkbox"/>	
Grab bars are placed horizontally at 36" above the floor line	<input type="checkbox"/>	<input type="checkbox"/>	

PICNICKING <i>N/A</i>			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
A minimum of 5% of the total tables must be accessible with clear space under the tabletop not less than 30" wide and 19" deep per seating space and not less than 27" clear from the ground to the underside of the table. An additional 29" clear space (totaling 48") must extend beyond the 19" clear space under the table to provide access	<input type="checkbox"/>	<input type="checkbox"/>	
For tables without toe clearance, the knee space under the table must be at least 28" high, 30" wide and 24" deep.	<input type="checkbox"/>	<input type="checkbox"/>	
Top of table no higher than 32" above ground	<input type="checkbox"/>	<input type="checkbox"/>	
Surface of the clear ground space under and around the table must be stable, firm and slip-resistant, and evenly graded with a maximum slope of 2% in all directions	<input type="checkbox"/>	<input type="checkbox"/>	
Accessible tables, grills and fire rings must have clear ground space of at least 36" around the perimeter	<input type="checkbox"/>	<input type="checkbox"/>	

ADA FACILITY INVENTORY

LOCATION: *Falls Pond Beach + Boat Ramp*

ACTIVITY	EQUIPMENT	NOTES
Picnic Facilities	Tables & Benches	<input checked="" type="checkbox"/> Located adjacent to accessible paths
		<input type="checkbox"/> Access to Open Spaces
		<input checked="" type="checkbox"/> Back and Arm Rests <i>no</i>
		<input checked="" type="checkbox"/> Adequate number
	Grills <i>NA</i>	<input type="checkbox"/> Height of Cooking Surface
		<input type="checkbox"/> Located adjacent to accessible paths
	Trash Cans	<input checked="" type="checkbox"/> Located adjacent to accessible paths
	<i>N/A</i> Picnic Shelters	<input type="checkbox"/> Located adjacent to accessible paths
<input type="checkbox"/> Located near accessible infrastructure and amenities		
Trails	<i>NA</i>	<input type="checkbox"/> Surface material
		<input type="checkbox"/> Dimensions
		<input type="checkbox"/> Rails
		<input type="checkbox"/> Accessible signage
Swimming Facilities	Pools <i>N/A</i>	<input type="checkbox"/> Entrance
		<input type="checkbox"/> Location from accessible parking
		<input type="checkbox"/> Safety features
	Beaches	<input checked="" type="checkbox"/> Location from accessible path into water
		<input type="checkbox"/> Handrails <i>no</i>
		<input checked="" type="checkbox"/> Location from accessible parking
		<input checked="" type="checkbox"/> Shade provided
		<input type="checkbox"/> Same experience provided to all
Play Areas	Play Equipment <i>N/A</i>	<input type="checkbox"/> Located adjacent to accessible paths
	<i>N/A</i> Access Routes	<input type="checkbox"/> Enough space between equipment for wheelchair
		<input type="checkbox"/> Located adjacent to accessible paths
Game Areas	<i>N/A</i> Access Routes	<input type="checkbox"/> Berm cuts onto courts
		<input type="checkbox"/> Height
	<i>N/A</i> Equipment	<input type="checkbox"/> Dimensions
		<input type="checkbox"/> Spectator Seating

Boat Docks <i>N/A</i>	Access Routes	<input type="checkbox"/> Located adjacent to accessible paths
		<input type="checkbox"/> Handrails
Fishing Facilities <i>*</i>	Access Routes	<input type="checkbox"/> Located adjacent to accessible paths
		<input type="checkbox"/> Handrails <i>no</i>
	Equipment <i>N/A</i>	<input type="checkbox"/> Arm Rests
		<input type="checkbox"/> Bait Shelves
		<input type="checkbox"/> Handrails
<input type="checkbox"/> Fish Cleaning Tables		
Programming	<input checked="" type="checkbox"/> Learn-to-Swim <i>offered</i>	
	<input type="checkbox"/> Guided Hikes	
	<input type="checkbox"/> Interpretive Programs	
Services	<input checked="" type="checkbox"/> Information available in alternative formats <i>website</i>	
	<input checked="" type="checkbox"/> Process to request interpretive services <i>website</i>	

PARKING			
TOTAL SPACES		REQUIRED ACCESSIBLE SPACES	
Up to 25	<input type="checkbox"/>	1 space	
26-50	<input type="checkbox"/>	2 spaces	
51-75	<input checked="" type="checkbox"/>	3 spaces	
76-100	<input type="checkbox"/>	4 spaces	
101-150	<input type="checkbox"/>	5 spaces	
151-200	<input type="checkbox"/>	6 spaces	
201-300	<input type="checkbox"/>	7 spaces	
301-400	<input type="checkbox"/>	8 spaces	
401-500	<input type="checkbox"/>	9 spaces	
ACCESSIBLE SPACE SPECIFICATIONS	YES	NO	COMMENTS/TRANSITION NOTES
Accessible space located closest to accessible entrance	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Where spaces cannot be located within 200 ft of accessible entrance, drop-off area is provided within 100 ft.	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Minimum width of 13 ft includes 8 ft space plus 5 ft access aisle	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Van space – minimum of 1 van space for every accessible space, 8 ft wide plus 8 ft aisle. Alternative is to make all accessible spaces 11 ft wide with 5 ft aisle.	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Sign with international symbol of accessibility at each space or pair of spaces	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Sign minimum 5 ft, maximum 8 ft to top of sign	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Surface evenly paved or hard-packed (no cracks)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Surface slope less than 1:20, 5%	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Curbcut to pathway from parking lot at each space or pair of spaces, if sidewalk (curb) is present	<input type="checkbox"/>	<input type="checkbox"/>	
Curbcut is a minimum width of 3 ft, excluding sloped sides, has sloped sides, all slopes not to exceed 1:12, and textured or painted yellow	<input type="checkbox"/>	<input type="checkbox"/>	

RAMPS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Slope Maximum 1:12	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Minimum width 4 ft between handrails	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<i>no handrail</i>
Handrails on both sides if ramp is longer than 6 ft	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Handrails at 34" and 19" from ramp surface	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Handrails extend 12" beyond top and bottom	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Handgrip oval or round	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Handgrip smooth surface	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Handgrip diameter between 1½" and 2"	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Clearance of 1½" between wall and wall rail	<input type="checkbox"/>	<input type="checkbox"/>	
Non-slip surface	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Level platforms (4ft x 4 ft) at every 30 ft, at top, at bottom, at change of direction	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

SITE ACCESS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Accessible path of travel from passenger disembarking area and parking area to accessible entrance	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Disembarking area at accessible entrance	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Surface evenly paved or hard-packed	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
No ponding of water	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

PATH OF TRAVEL			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Path does not require the use of stairs	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Path is stable, firm and slip resistant	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
3 ft wide minimum	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Slope maximum 1:20 (5%) and maximum cross pitch is 2% (1:50).	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Continuous common surface, no changes in level greater than ½ inch	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Any objects protruding onto the pathway must be detected by a person with a visual disability using a cane	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

PATH OF TRAVEL			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Objects protruding more than 4" from the wall must be within 27" of the ground, or higher than 80"	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Curb on the pathway must have curb cuts at drives, parking and drop-offs	<input type="checkbox"/>	<input type="checkbox"/>	N/A

ENTRANCES <i>No Intern Facilities</i>			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Primary public entrances accessible to person using wheelchair, must be signed, gotten to independently, and <i>not</i> be the service entrance	<input type="checkbox"/>	<input type="checkbox"/>	
Level space extending 5 ft. from the door, interior and exterior of entrance doors	<input type="checkbox"/>	<input type="checkbox"/>	
Minimum 32" clear width opening (i.e. 36" door with standard hinge)	<input type="checkbox"/>	<input type="checkbox"/>	
At least 18" clear floor area on latch, pull side of door	<input type="checkbox"/>	<input type="checkbox"/>	
Door handle no higher than 48" and operable with a closed fist	<input type="checkbox"/>	<input type="checkbox"/>	
Vestibule is 4 ft plus the width of the door swinging into the space	<input type="checkbox"/>	<input type="checkbox"/>	
Entrance(s) on a level that makes elevators accessible	<input type="checkbox"/>	<input type="checkbox"/>	
Door mats less than ½" thick are securely fastened	<input type="checkbox"/>	<input type="checkbox"/>	
Door mats more than ½" thick are recessed	<input type="checkbox"/>	<input type="checkbox"/>	
Grates in path of travel have openings of ½" maximum	<input type="checkbox"/>	<input type="checkbox"/>	
Signs at non-accessible entrance(s) indicate direction to accessible entrance	<input type="checkbox"/>	<input type="checkbox"/>	
Emergency egress – alarms with flashing lights and audible signals, sufficiently lighted	<input type="checkbox"/>	<input type="checkbox"/>	

STAIRS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
No open risers	<input type="checkbox"/>	<input type="checkbox"/>	
Nosings not projecting	<input type="checkbox"/>	<input type="checkbox"/>	
Treads no less than 11" wide	<input type="checkbox"/>	<input type="checkbox"/>	
Handrails on both sides	<input type="checkbox"/>	<input type="checkbox"/>	
Handrails 34"-38" above tread	<input type="checkbox"/>	<input type="checkbox"/>	
Handrail extends a minimum of 1 ft beyond top and bottom riser (if no safety hazard and space permits)	<input type="checkbox"/>	<input type="checkbox"/>	
Handgrip oval or round	<input type="checkbox"/>	<input type="checkbox"/>	
Handgrip has a smooth surface	<input type="checkbox"/>	<input type="checkbox"/>	
Handgrip diameter between 1¼" and 1½"	<input type="checkbox"/>	<input type="checkbox"/>	
1½" clearance between wall and handrail	<input type="checkbox"/>	<input type="checkbox"/>	

DOORS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Minimum 32" clear opening	<input type="checkbox"/>	<input type="checkbox"/>	
At least 18" clear floor space on pull side of door	<input type="checkbox"/>	<input type="checkbox"/>	
Closing speed minimum 3 seconds to within 3" of the latch	<input type="checkbox"/>	<input type="checkbox"/>	
Maximum pressure 5 pounds interior doors	<input type="checkbox"/>	<input type="checkbox"/>	
Threshold maximum ½" high, beveled on both sides	<input type="checkbox"/>	<input type="checkbox"/>	
Hardware operable with a closed fist (no conventional doorknobs or thumb latch devices)	<input type="checkbox"/>	<input type="checkbox"/>	
Hardware minimum 36", maximum 48" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
Clear, level floor space extends out 5 ft from both sides of the door	<input type="checkbox"/>	<input type="checkbox"/>	
Door adjacent to revolving door is accessible and unlocked	<input type="checkbox"/>	<input type="checkbox"/>	
Doors opening into hazardous area have hardware that is knurled or roughened	<input type="checkbox"/>	<input type="checkbox"/>	

RESTROOMS <i>accessible Portajohns only</i>			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
5 ft turning space measured 12" from the floor	<input type="checkbox"/>	<input type="checkbox"/>	
AT LEAST ONE SINK			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Clear floor space of 30" by 48" to allow a forward approach	<input type="checkbox"/>	<input type="checkbox"/>	
Mounted without pedestal or legs, height 34" to top of rim	<input type="checkbox"/>	<input type="checkbox"/>	
Extends at least 22" from the wall	<input type="checkbox"/>	<input type="checkbox"/>	
Open knee space a minimum 19" deep, 30" width, and 27" high	<input type="checkbox"/>	<input type="checkbox"/>	
Cover exposed pipes with insulation	<input type="checkbox"/>	<input type="checkbox"/>	
Faucets operable with closed fist (lever or spring activated handle)	<input type="checkbox"/>	<input type="checkbox"/>	
AT LEAST ONE STALL			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Accessible to person using wheelchair at 60" wide by 72" deep	<input type="checkbox"/>	<input type="checkbox"/>	
Stall door is 36" wide	<input type="checkbox"/>	<input type="checkbox"/>	
Stall door swings out	<input type="checkbox"/>	<input type="checkbox"/>	
Stall door is self closing	<input type="checkbox"/>	<input type="checkbox"/>	
Stall door has a pull latch	<input type="checkbox"/>	<input type="checkbox"/>	
Lock on stall door is operable with a closed fist, and 32" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
Coat hook is 54" high	<input type="checkbox"/>	<input type="checkbox"/>	
TOILET			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
18" from center to nearest side wall	<input type="checkbox"/>	<input type="checkbox"/>	
42" minimum clear space from center to farthest wall or fixture	<input type="checkbox"/>	<input type="checkbox"/>	
Top of seat 17"-19" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
GRAB BARS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
On back and side wall closest to toilet	<input type="checkbox"/>	<input type="checkbox"/>	
1 1/4" diameter	<input type="checkbox"/>	<input type="checkbox"/>	
1 1/2" clearance to wall	<input type="checkbox"/>	<input type="checkbox"/>	
Located 30" above and parallel to the floor	<input type="checkbox"/>	<input type="checkbox"/>	
Acid-etched or roughened grab bar surface	<input type="checkbox"/>	<input type="checkbox"/>	
42" long grab bars	<input type="checkbox"/>	<input type="checkbox"/>	

RESTROOMS			
FIXTURES			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Toilet paper dispenser is 24" above floor	<input type="checkbox"/>	<input type="checkbox"/>	
One mirror set a maximum 38" to bottom (if tilted, 42")	<input type="checkbox"/>	<input type="checkbox"/>	
Dispensers (towel, soap, etc.) at least one of each a maximum 42" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	

FLOORS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Non-slip surface	<input type="checkbox"/>	<input type="checkbox"/>	
Carpeting is high-density, low pile, non-absorbent, stretched taut, securely anchored	<input type="checkbox"/>	<input type="checkbox"/>	
Corridor width minimum is 3 ft	<input type="checkbox"/>	<input type="checkbox"/>	
Objects (signs, ceiling lights, fixtures) can only protrude 4" into the path of travel from a height of 27" to 80" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	

DRINKING FOUNTAINS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Spouts no higher than 36" from floor to outlet	<input type="checkbox"/>	<input type="checkbox"/>	
Hand operated push button or level controls	<input type="checkbox"/>	<input type="checkbox"/>	
Spouts located near front with stream of water as parallel to front as possible	<input type="checkbox"/>	<input type="checkbox"/>	
If recessed, recess a minimum 30" width, and no deeper than depth of fountain	<input type="checkbox"/>	<input type="checkbox"/>	
If no clear knee space underneath, clear floor space 30" x 48" to allow parallel approach	<input type="checkbox"/>	<input type="checkbox"/>	

TELEPHONES			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Highest operating part a maximum 54" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
Access within 12" of phone, 30" high by 30" wide	<input type="checkbox"/>	<input type="checkbox"/>	
Adjustable volume control on headset so identified	<input type="checkbox"/>	<input type="checkbox"/>	

SIGNALS, OUTLETS, AND SWITCHES			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Switches and controls for light, heat, ventilation, windows, fire alarms, thermostats, etc., must be a minimum of 36" and a maximum of 48" above the floor for a forward reach, a maximum of 54" for a side reach	<input type="checkbox"/>	<input type="checkbox"/>	
Electrical outlets centered no lower than 18" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
Warning signals must be visual as well as audible	<input type="checkbox"/>	<input type="checkbox"/>	

SIGNS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Mounting height must be 60" to centerline of the sign	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Within 18" of door jamb or recessed	<input type="checkbox"/>	<input type="checkbox"/>	n/a
Letters and numbers at least 1/4" high	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Letters and numbers raised .03"	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Letters and numbers contrast with the background color	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

SWIMMING POOLS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Ramp at least 34" wide with a non-slip surface extending into the shallow end, slope not exceeding 1:6 with handrails on both sides	<input type="checkbox"/>	<input type="checkbox"/>	<i>Note: Pools may accommodate either ramp or lifting access.</i>
Lifting device	<input type="checkbox"/>	<input type="checkbox"/>	<i>Note: Pools may accommodate either ramp or lifting access.</i>
Transfer area 18" above the path of travel and a minimum of 18" wide	<input type="checkbox"/>	<input type="checkbox"/>	
Unobstructed path of travel not less than 48" wide around pool	<input type="checkbox"/>	<input type="checkbox"/>	
Non-slip surface	<input type="checkbox"/>	<input type="checkbox"/>	

SHOWER ROOMS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Stalls 36" by 60" minimum, with a 36" door opening	<input type="checkbox"/>	<input type="checkbox"/>	<i>Note: Showers must accommodate both wheel-in and transfer use</i>
Floors are pitched to drain the stall at the corner farthest from entrance	<input type="checkbox"/>	<input type="checkbox"/>	
Floors are non-slip surface	<input type="checkbox"/>	<input type="checkbox"/>	
Controls operate by a single lever with a pressure balance mixing valve	<input type="checkbox"/>	<input type="checkbox"/>	

Controls are located on the center wall adjacent to the hinged seat	<input type="checkbox"/>	<input type="checkbox"/>	
Shower heads attached to a flexible metal hose	<input type="checkbox"/>	<input type="checkbox"/>	
Shower heads attached to wall mounting adjustable from 42" to 72" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
Seat is hinged and padded and at least 16" deep, folds upward, securely attached to side wall, height is 18" to the top of the seat, and at least 24" long	<input type="checkbox"/>	<input type="checkbox"/>	
Soap trays without handhold features unless they can support 250 pounds	<input type="checkbox"/>	<input type="checkbox"/>	
2 grab bars are provided, one 30" and one 48" long, or one continuous L shaped bar	<input type="checkbox"/>	<input type="checkbox"/>	
Grab bars are placed horizontally at 36" above the floor line	<input type="checkbox"/>	<input type="checkbox"/>	

PICNICKING			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
A minimum of 5% of the total tables must be accessible with clear space under the tabletop not less than 30" wide and 19" deep per seating space and not less than 27" clear from the ground to the underside of the table. An additional 29" clear space (totaling 48") must extend beyond the 19" clear space under the table to provide access	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<i>2 picnic tables</i>
For tables without toe clearance, the knee space under the table must be at least 28" high, 30" wide and 24" deep.	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Top of table no higher than 32" above ground	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Surface of the clear ground space under and around the table must be stable, firm and slip-resistant, and evenly graded with a maximum slope of 2% in all directions	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<i>on sand area</i>
Accessible tables, grills and fire rings must have clear ground space of at least 36" around the perimeter	<input type="checkbox"/>	<input type="checkbox"/>	<i>N/A</i>

ADA FACILITY INVENTORY

LOCATION: *Chorney Property*

ACTIVITY	EQUIPMENT	NOTES
Picnic Facilities <i>N/A</i>	Tables & Benches	<input type="checkbox"/> Located adjacent to accessible paths
		<input type="checkbox"/> Access to Open Spaces
		<input type="checkbox"/> Back and Arm Rests
		<input type="checkbox"/> Adequate number
	Grills	<input type="checkbox"/> Height of Cooking Surface
		<input type="checkbox"/> Located adjacent to accessible paths
	Trash Cans	<input type="checkbox"/> Located adjacent to accessible paths
	Picnic Shelters	<input type="checkbox"/> Located adjacent to accessible paths
<input type="checkbox"/> Located near accessible infrastructure and amenities		
Trails <i>✱</i>	<i>walking bridge across wetland</i>	<input type="checkbox"/> Surface material —
		<input type="checkbox"/> Dimensions —
		<input type="checkbox"/> Rails —
		<input type="checkbox"/> Accessible signage —
Swimming Facilities <i>N/A</i>	Pools	<input type="checkbox"/> Entrance
		<input type="checkbox"/> Location from accessible parking
		<input type="checkbox"/> Safety features
	Beaches	<input type="checkbox"/> Location from accessible path into water
		<input type="checkbox"/> Handrails
		<input type="checkbox"/> Location from accessible parking
		<input type="checkbox"/> Shade provided
	Play Areas <i>N/A</i>	Play Equipment
Access Routes		<input type="checkbox"/> Located adjacent to accessible paths
	<input type="checkbox"/> Enough space between equipment for wheelchair	
Game Areas <i>N/A</i>	Access Routes	<input type="checkbox"/> Located adjacent to accessible paths
		<input type="checkbox"/> Berm cuts onto courts
	Equipment	<input type="checkbox"/> Height
		<input type="checkbox"/> Dimensions
		<input type="checkbox"/> Spectator Seating

Boat Docks <i>N/A</i>	Access Routes	<input type="checkbox"/> Located adjacent to accessible paths
		<input type="checkbox"/> Handrails
Fishing Facilities <i>N/A</i>	Access Routes	<input type="checkbox"/> Located adjacent to accessible paths
		<input type="checkbox"/> Handrails
	Equipment	<input type="checkbox"/> Arm Rests
		<input type="checkbox"/> Bait Shelves
		<input type="checkbox"/> Handrails
<input type="checkbox"/> Fish Cleaning Tables		
Programming <i>N/A</i>	<input type="checkbox"/> Learn-to-Swim	
	<input type="checkbox"/> Guided Hikes	
	<input type="checkbox"/> Interpretive Programs	
Services <i>N/A</i>	<input type="checkbox"/> Information available in alternative formats	
	<input type="checkbox"/> Process to request interpretive services	

PARKING			
TOTAL SPACES		REQUIRED ACCESSIBLE SPACES	
Up to 25	<input checked="" type="checkbox"/>	1 space	<i>gravel parking lot</i>
26-50	<input type="checkbox"/>	2 spaces	
51-75	<input type="checkbox"/>	3 spaces	
76-100	<input type="checkbox"/>	4 spaces	
101-150	<input type="checkbox"/>	5 spaces	
151-200	<input type="checkbox"/>	6 spaces	
201-300	<input type="checkbox"/>	7 spaces	
301-400	<input type="checkbox"/>	8 spaces	
401-500	<input type="checkbox"/>	9 spaces	
ACCESSIBLE SPACE SPECIFICATIONS	YES	NO	COMMENTS/TRANSITION NOTES
Accessible space located closest to accessible entrance	<input type="checkbox"/>	<input type="checkbox"/>	<i>gravel parking no accessible entrance</i>
Where spaces cannot be located within 200 ft of accessible entrance, drop-off area is provided within 100 ft.	<input type="checkbox"/>	<input type="checkbox"/>	<i>" "</i>
Minimum width of 13 ft includes 8 ft space plus 5 ft access aisle	<input type="checkbox"/>	<input type="checkbox"/>	<i>" "</i>
Van space – minimum of 1 van space for every accessible space, 8 ft wide plus 8 ft aisle. Alternative is to make all accessible spaces 11 ft wide with 5 ft aisle.	<input type="checkbox"/>	<input type="checkbox"/>	<i>" "</i>
Sign with international symbol of accessibility at each space or pair of spaces	<input type="checkbox"/>	<input type="checkbox"/>	<i>no signage</i>
Sign minimum 5 ft, maximum 8 ft to top of sign	<input type="checkbox"/>	<input type="checkbox"/>	<i>no signage</i>
Surface evenly paved or hard-packed (no cracks)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Surface slope less than 1:20, 5%	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Curbside to pathway from parking lot at each space or pair of spaces, if sidewalk (curb) is present	<input type="checkbox"/>	<input type="checkbox"/>	<i>n/a</i>
Curbside is a minimum width of 3 ft, excluding sloped sides, has sloped sides, all slopes not to exceed 1:12, and textured or painted yellow	<input type="checkbox"/>	<input type="checkbox"/>	<i>n/a</i>

RAMPS <i>Walking Bridge</i>			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Slope Maximum 1:12	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Minimum width 4 ft between handrails	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<i>no handrail</i>
Handrails on both sides if ramp is longer than 6 ft	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<i>"</i>
Handrails at 34" and 19" from ramp surface	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<i>"</i>
Handrails extend 12" beyond top and bottom	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<i>"</i>
Handgrip oval or round	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<i>"</i>
Handgrip smooth surface	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<i>"</i>
Handgrip diameter between 1 1/4" and 2"	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<i>"</i>
Clearance of 1 1/2" between wall and wall rail	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<i>"</i>
Non-slip surface	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Level platforms (4ft x 4 ft) at every 30 ft, at top, at bottom, at change of direction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<i>need platforms</i>

SITE ACCESS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Accessible path of travel from passenger disembarking area and parking area to accessible entrance	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Disembarking area at accessible entrance	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Surface evenly paved or hard-packed	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
No ponding of water	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

PATH OF TRAVEL			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Path does not require the use of stairs	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<i>gravel - field - winds over bridge</i>
Path is stable, firm and slip resistant	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<i>not stable, uneven</i>
3 ft wide minimum	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Slope maximum 1:20 (5%) and maximum cross pitch is 2% (1:50).	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<i>bridge slope ok trail has slope</i>
Continuous common surface, no changes in level greater than 1/2 inch	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<i>bridge ok trail has changes in surface</i>
Any objects protruding onto the pathway must be detected by a person with a visual disability using a cane	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<i>trail may have protruding objects, needs maintenance</i>

PATH OF TRAVEL			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Objects protruding more than 4" from the wall must be within 27" of the ground, or higher than 80"	<input type="checkbox"/>	<input type="checkbox"/>	
Curb on the pathway must have curb cuts at drives, parking and drop-offs	<input type="checkbox"/>	<input type="checkbox"/>	

ENTRANCES <i>No interior facilities</i>			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Primary public entrances accessible to person using wheelchair, must be signed, gotten to independently, and <i>not</i> be the service entrance	<input type="checkbox"/>	<input type="checkbox"/>	
Level space extending 5 ft. from the door, interior and exterior of entrance doors	<input type="checkbox"/>	<input type="checkbox"/>	
Minimum 32" clear width opening (i.e. 36" door with standard hinge)	<input type="checkbox"/>	<input type="checkbox"/>	
At least 18" clear floor area on latch, pull side of door	<input type="checkbox"/>	<input type="checkbox"/>	
Door handle no higher than 48" and operable with a closed fist	<input type="checkbox"/>	<input type="checkbox"/>	
Vestibule is 4 ft plus the width of the door swinging into the space	<input type="checkbox"/>	<input type="checkbox"/>	
Entrance(s) on a level that makes elevators accessible	<input type="checkbox"/>	<input type="checkbox"/>	
Door mats less than ½" thick are securely fastened	<input type="checkbox"/>	<input type="checkbox"/>	
Door mats more than ½" thick are recessed	<input type="checkbox"/>	<input type="checkbox"/>	
Grates in path of travel have openings of ½" maximum	<input type="checkbox"/>	<input type="checkbox"/>	
Signs at non-accessible entrance(s) indicate direction to accessible entrance	<input type="checkbox"/>	<input type="checkbox"/>	
Emergency egress – alarms with flashing lights and audible signals, sufficiently lighted	<input type="checkbox"/>	<input type="checkbox"/>	

STAIRS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
No open risers	<input type="checkbox"/>	<input type="checkbox"/>	
Nosings not projecting	<input type="checkbox"/>	<input type="checkbox"/>	
Treads no less than 11" wide	<input type="checkbox"/>	<input type="checkbox"/>	
Handrails on both sides	<input type="checkbox"/>	<input type="checkbox"/>	
Handrails 34"-38" above tread	<input type="checkbox"/>	<input type="checkbox"/>	
Handrail extends a minimum of 1 ft beyond top and bottom riser (if no safety hazard and space permits)	<input type="checkbox"/>	<input type="checkbox"/>	
Handgrip oval or round	<input type="checkbox"/>	<input type="checkbox"/>	
Handgrip has a smooth surface	<input type="checkbox"/>	<input type="checkbox"/>	
Handgrip diameter between 1¼" and 1½"	<input type="checkbox"/>	<input type="checkbox"/>	
1½" clearance between wall and handrail	<input type="checkbox"/>	<input type="checkbox"/>	

DOORS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Minimum 32" clear opening	<input type="checkbox"/>	<input type="checkbox"/>	
At least 18" clear floor space on pull side of door	<input type="checkbox"/>	<input type="checkbox"/>	
Closing speed minimum 3 seconds to within 3" of the latch	<input type="checkbox"/>	<input type="checkbox"/>	
Maximum pressure 5 pounds interior doors	<input type="checkbox"/>	<input type="checkbox"/>	
Threshold maximum ½" high, beveled on both sides	<input type="checkbox"/>	<input type="checkbox"/>	
Hardware operable with a closed fist (no conventional doorknobs or thumb latch devices)	<input type="checkbox"/>	<input type="checkbox"/>	
Hardware minimum 36", maximum 48" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
Clear, level floor space extends out 5 ft from both sides of the door	<input type="checkbox"/>	<input type="checkbox"/>	
Door adjacent to revolving door is accessible and unlocked	<input type="checkbox"/>	<input type="checkbox"/>	
Doors opening into hazardous area have hardware that is knurled or roughened	<input type="checkbox"/>	<input type="checkbox"/>	

RESTROOMS <i>No restrooms</i>			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
5 ft turning space measured 12" from the floor	<input type="checkbox"/>	<input type="checkbox"/>	
AT LEAST ONE SINK			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Clear floor space of 30" by 48" to allow a forward approach	<input type="checkbox"/>	<input type="checkbox"/>	
Mounted without pedestal or legs, height 34" to top of rim	<input type="checkbox"/>	<input type="checkbox"/>	
Extends at least 22" from the wall	<input type="checkbox"/>	<input type="checkbox"/>	
Open knee space a minimum 19" deep, 30" width, and 27" high	<input type="checkbox"/>	<input type="checkbox"/>	
Cover exposed pipes with insulation	<input type="checkbox"/>	<input type="checkbox"/>	
Faucets operable with closed fist (lever or spring activated handle)	<input type="checkbox"/>	<input type="checkbox"/>	
AT LEAST ONE STALL			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Accessible to person using wheelchair at 60" wide by 72" deep	<input type="checkbox"/>	<input type="checkbox"/>	
Stall door is 36" wide	<input type="checkbox"/>	<input type="checkbox"/>	
Stall door swings out	<input type="checkbox"/>	<input type="checkbox"/>	
Stall door is self closing	<input type="checkbox"/>	<input type="checkbox"/>	
Stall door has a pull latch	<input type="checkbox"/>	<input type="checkbox"/>	
Lock on stall door is operable with a closed fist, and 32" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
Coat hook is 54" high	<input type="checkbox"/>	<input type="checkbox"/>	
TOILET			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
18" from center to nearest side wall	<input type="checkbox"/>	<input type="checkbox"/>	
42" minimum clear space from center to farthest wall or fixture	<input type="checkbox"/>	<input type="checkbox"/>	
Top of seat 17"-19" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
GRAB BARS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
On back and side wall closest to toilet	<input type="checkbox"/>	<input type="checkbox"/>	
1 1/4" diameter	<input type="checkbox"/>	<input type="checkbox"/>	
1 1/2" clearance to wall	<input type="checkbox"/>	<input type="checkbox"/>	
Located 30" above and parallel to the floor	<input type="checkbox"/>	<input type="checkbox"/>	
Acid-etched or roughened grab bar surface	<input type="checkbox"/>	<input type="checkbox"/>	
42" long grab bars	<input type="checkbox"/>	<input type="checkbox"/>	

RESTROOMS			
FIXTURES			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Toilet paper dispenser is 24" above floor	<input type="checkbox"/>	<input type="checkbox"/>	
One mirror set a maximum 38" to bottom (if tilted, 42")	<input type="checkbox"/>	<input type="checkbox"/>	
Dispensers (towel, soap, etc.) at least one of each a maximum 42" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	

FLOORS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Non-slip surface	<input type="checkbox"/>	<input type="checkbox"/>	
Carpeting is high-density, low pile, non-absorbent, stretched taut, securely anchored	<input type="checkbox"/>	<input type="checkbox"/>	
Corridor width minimum is 3 ft	<input type="checkbox"/>	<input type="checkbox"/>	
Objects (signs, ceiling lights, fixtures) can only protrude 4" into the path of travel from a height of 27" to 80" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	

DRINKING FOUNTAINS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Spouts no higher than 36" from floor to outlet	<input type="checkbox"/>	<input type="checkbox"/>	
Hand operated push button or level controls	<input type="checkbox"/>	<input type="checkbox"/>	
Spouts located near front with stream of water as parallel to front as possible	<input type="checkbox"/>	<input type="checkbox"/>	
If recessed, recess a minimum 30" width, and no deeper than depth of fountain	<input type="checkbox"/>	<input type="checkbox"/>	
If no clear knee space underneath, clear floor space 30" x 48" to allow parallel approach	<input type="checkbox"/>	<input type="checkbox"/>	

TELEPHONES			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Highest operating part a maximum 54" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
Access within 12" of phone, 30" high by 30" wide	<input type="checkbox"/>	<input type="checkbox"/>	
Adjustable volume control on headset so identified	<input type="checkbox"/>	<input type="checkbox"/>	

SIGNALS, OUTLETS, AND SWITCHES			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Switches and controls for light, heat, ventilation, windows, fire alarms, thermostats, etc., must be a minimum of 36" and a maximum of 48" above the floor for a forward reach, a maximum of 54" for a side reach	<input type="checkbox"/>	<input type="checkbox"/>	
Electrical outlets centered no lower than 18" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
Warning signals must be visual as well as audible	<input type="checkbox"/>	<input type="checkbox"/>	

SIGNS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Mounting height must be 60" to centerline of the sign	<input type="checkbox"/>	<input type="checkbox"/>	
Within 18" of door jamb or recessed	<input type="checkbox"/>	<input type="checkbox"/>	
Letters and numbers at least 1/4" high	<input type="checkbox"/>	<input type="checkbox"/>	
Letters and numbers raised .03"	<input type="checkbox"/>	<input type="checkbox"/>	
Letters and numbers contrast with the background color	<input type="checkbox"/>	<input type="checkbox"/>	

SWIMMING POOLS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Ramp at least 34" wide with a non-slip surface extending into the shallow end, slope not exceeding 1:6 with handrails on both sides	<input type="checkbox"/>	<input type="checkbox"/>	<i>Note: Pools may accommodate either ramp or lifting access.</i>
Lifting device	<input type="checkbox"/>	<input type="checkbox"/>	<i>Note: Pools may accommodate either ramp or lifting access.</i>
Transfer area 18" above the path of travel and a minimum of 18" wide	<input type="checkbox"/>	<input type="checkbox"/>	
Unobstructed path of travel not less than 48" wide around pool	<input type="checkbox"/>	<input type="checkbox"/>	
Non-slip surface	<input type="checkbox"/>	<input type="checkbox"/>	

SHOWER ROOMS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Stalls 36" by 60" minimum, with a 36" door opening	<input type="checkbox"/>	<input type="checkbox"/>	<i>Note: Showers must accommodate both wheel-in and transfer use</i>
Floors are pitched to drain the stall at the corner farthest from entrance	<input type="checkbox"/>	<input type="checkbox"/>	
Floors are non-slip surface	<input type="checkbox"/>	<input type="checkbox"/>	
Controls operate by a single lever with a pressure balance mixing valve	<input type="checkbox"/>	<input type="checkbox"/>	

Controls are located on the center wall adjacent to the hinged seat	<input type="checkbox"/>	<input type="checkbox"/>	
Shower heads attached to a flexible metal hose	<input type="checkbox"/>	<input type="checkbox"/>	
Shower heads attached to wall mounting adjustable from 42" to 72" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
Seat is hinged and padded and at least 16" deep, folds upward, securely attached to side wall, height is 18" to the top of the seat, and at least 24" long	<input type="checkbox"/>	<input type="checkbox"/>	
Soap trays without handhold features unless they can support 250 pounds	<input type="checkbox"/>	<input type="checkbox"/>	
2 grab bars are provided, one 30" and one 48" long, or one continuous L shaped bar	<input type="checkbox"/>	<input type="checkbox"/>	
Grab bars are placed horizontally at 36" above the floor line	<input type="checkbox"/>	<input type="checkbox"/>	

PICNICKING			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
A minimum of 5% of the total tables must be accessible with clear space under the tabletop not less than 30" wide and 19" deep per seating space and not less than 27" clear from the ground to the underside of the table. An additional 29" clear space (totaling 48") must extend beyond the 19" clear space under the table to provide access	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
For tables without toe clearance, the knee space under the table must be at least 28" high, 30" wide and 24" deep.	<input type="checkbox"/>	<input type="checkbox"/>	
Top of table no higher than 32" above ground	<input type="checkbox"/>	<input type="checkbox"/>	
Surface of the clear ground space under and around the table must be stable, firm and slip-resistant, and evenly graded with a maximum slope of 2% in all directions	<input type="checkbox"/>	<input type="checkbox"/>	
Accessible tables, grills and fire rings must have clear ground space of at least 36" around the perimeter	<input type="checkbox"/>	<input type="checkbox"/>	

ADA FACILITY INVENTORY

LOCATION: *WNI Park & Zoo*

ACTIVITY	EQUIPMENT	NOTES
Picnic Facilities	Tables & Benches	<input checked="" type="checkbox"/> Located adjacent to accessible paths
		<input checked="" type="checkbox"/> Access to Open Spaces
		<input checked="" type="checkbox"/> Back and Arm Rests
		<input checked="" type="checkbox"/> Adequate number
	Grills	<input checked="" type="checkbox"/> Height of Cooking Surface
		<input checked="" type="checkbox"/> Located adjacent to accessible paths
	Trash Cans	<input checked="" type="checkbox"/> Located adjacent to accessible paths
	Picnic Shelters	<input type="checkbox"/> Located adjacent to accessible paths
<input type="checkbox"/> Located near accessible infrastructure and amenities <i>N/A</i>		
Trails		<input checked="" type="checkbox"/> Surface material <i>gravel</i>
		<input checked="" type="checkbox"/> Dimensions <i>10ft wide</i>
		<input type="checkbox"/> Rails <i>N/A</i>
		<input checked="" type="checkbox"/> Accessible signage
Swimming Facilities	Pools	<input type="checkbox"/> Entrance
		<input type="checkbox"/> Location from accessible parking <i>N/A</i>
		<input type="checkbox"/> Safety features
	Beaches	<input type="checkbox"/> Location from accessible path into water
		<input type="checkbox"/> Handrails
		<input type="checkbox"/> Location from accessible parking <i>N/A</i>
Play Areas	Play Equipment	<input checked="" type="checkbox"/> Same experience provided to all
	Access Routes	<input checked="" type="checkbox"/> Located adjacent to accessible paths <input checked="" type="checkbox"/> Enough space between equipment for wheelchair
Game Areas	Access Routes	<input checked="" type="checkbox"/> Located adjacent to accessible paths
		<input checked="" type="checkbox"/> Berm cuts onto courts
	Equipment	<input checked="" type="checkbox"/> Height
		<input checked="" type="checkbox"/> Spectator Seating

Boat Docks	Access Routes	<input type="checkbox"/> Located adjacent to accessible paths	N/A
		<input type="checkbox"/> Handrails	
Fishing Facilities	Access Routes	<input type="checkbox"/> Located adjacent to accessible paths	N/A
		<input type="checkbox"/> Handrails	
	Equipment	<input type="checkbox"/> Arm Rests	
		<input type="checkbox"/> Bait Shelves	
		<input type="checkbox"/> Handrails	
<input type="checkbox"/> Fish Cleaning Tables			
Programming	<input type="checkbox"/> Learn-to-Swim		N/A
	<input type="checkbox"/> Guided Hikes		
	<input type="checkbox"/> Interpretive Programs		
Services	<input type="checkbox"/> Information available in alternative formats		N/A
	<input type="checkbox"/> Process to request interpretive services		

PARKING			
TOTAL SPACES	REQUIRED ACCESSIBLE SPACES		
Up to 25	<input type="checkbox"/>	1 space	
26-50	<input type="checkbox"/>	2 spaces	
51-75	<input type="checkbox"/>	3 spaces	
76-100	<input type="checkbox"/>	4 spaces	
101-150	<input type="checkbox"/>	5 spaces	
151-200	<input type="checkbox"/>	6 spaces	
201-300	<input checked="" type="checkbox"/>	7 spaces	
301-400	<input type="checkbox"/>	8 spaces	
401-500	<input type="checkbox"/>	9 spaces	
ACCESSIBLE SPACE SPECIFICATIONS	YES	NO	COMMENTS/TRANSITION NOTES
Accessible space located closest to accessible entrance	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Where spaces cannot be located within 200 ft of accessible entrance, drop-off area is provided within 100 ft.	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Minimum width of 13 ft includes 8 ft space plus 5 ft access aisle	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Van space – minimum of 1 van space for every accessible space, 8 ft wide plus 8 ft aisle. Alternative is to make all accessible spaces 11 ft wide with 5 ft aisle.	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Sign with international symbol of accessibility at each space or pair of spaces	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Sign minimum 5 ft, maximum 8 ft to top of sign	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Surface evenly paved or hard-packed (no cracks)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Surface slope less than 1:20, 5%	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Curbcut to pathway from parking lot at each space or pair of spaces, if sidewalk (curb) is present	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Curbcut is a minimum width of 3 ft, excluding sloped sides, has sloped sides, all slopes not to exceed 1:12, and textured or painted yellow	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

RAMPS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Slope Maximum 1:12	<input type="checkbox"/>	<input type="checkbox"/>	
Minimum width 4 ft between handrails	<input type="checkbox"/>	<input type="checkbox"/>	
Handrails on both sides if ramp is longer than 6 ft	<input type="checkbox"/>	<input type="checkbox"/>	
Handrails at 34" and 19" from ramp surface	<input type="checkbox"/>	<input type="checkbox"/>	
Handrails extend 12" beyond top and bottom	<input type="checkbox"/>	<input type="checkbox"/>	
Handgrip oval or round	<input type="checkbox"/>	<input type="checkbox"/>	NOT
Handgrip smooth surface	<input type="checkbox"/>	<input type="checkbox"/>	
Handgrip diameter between 1¼" and 2"	<input type="checkbox"/>	<input type="checkbox"/>	
Clearance of 1½" between wall and wall rail	<input type="checkbox"/>	<input type="checkbox"/>	
Non-slip surface	<input type="checkbox"/>	<input type="checkbox"/>	
Level platforms (4ft x 4 ft) at every 30 ft, at top, at bottom, at change of direction	<input type="checkbox"/>	<input type="checkbox"/>	

SITE ACCESS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Accessible path of travel from passenger disembarking area and parking area to accessible entrance	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Disembarking area at accessible entrance	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Surface evenly paved or hard-packed	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
No ponding of water	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

PATH OF TRAVEL			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Path does not require the use of stairs	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Path is stable, firm and slip resistant	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
3 ft wide minimum	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Slope maximum 1:20 (5%) and maximum cross pitch is 2% (1:50).	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Continuous common surface, no changes in level greater than ½ inch	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Any objects protruding onto the pathway must be detected by a person with a visual disability using a cane	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

PATH OF TRAVEL			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Objects protruding more than 4" from the wall must be within 27" of the ground, or higher than 80"	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Curb on the pathway must have curb cuts at drives, parking and drop-offs	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

ENTRANCES			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Primary public entrances accessible to person using wheelchair, must be signed, gotten to independently, and <i>not</i> be the service entrance	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Level space extending 5 ft. from the door, interior and exterior of entrance doors	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Minimum 32" clear width opening (i.e. 36" door with standard hinge)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
At least 18" clear floor area on latch, pull side of door	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Door handle no higher than 48" and operable with a closed fist	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Vestibule is 4 ft plus the width of the door swinging into the space	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Entrance(s) on a level that makes elevators accessible	<input checked="" type="checkbox"/>	<input type="checkbox"/>	N/A no elevators
Door mats less than 1/2" thick are securely fastened	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Door mats more than 1/2" thick are recessed	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Grates in path of travel have openings of 1/2" maximum	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Signs at non-accessible entrance(s) indicate direction to accessible entrance	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Emergency egress – alarms with flashing lights and audible signals, sufficiently lighted	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

STAIRS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
No open risers	<input type="checkbox"/>	<input type="checkbox"/>	
Nosings not projecting	<input type="checkbox"/>	<input type="checkbox"/>	
Treads no less than 11" wide	<input type="checkbox"/>	<input type="checkbox"/>	
Handrails on both sides	<input type="checkbox"/>	<input type="checkbox"/>	
Handrails 34"-38" above tread	<input type="checkbox"/>	<input type="checkbox"/>	
Handrail extends a minimum of 1 ft beyond top and bottom riser (if no safety hazard and space permits)	<input type="checkbox"/>	<input type="checkbox"/>	N/A no stairs
Handgrip oval or round	<input type="checkbox"/>	<input type="checkbox"/>	
Handgrip has a smooth surface	<input type="checkbox"/>	<input type="checkbox"/>	
Handgrip diameter between 1¼" and 1½"	<input type="checkbox"/>	<input type="checkbox"/>	
1½" clearance between wall and handrail	<input type="checkbox"/>	<input type="checkbox"/>	

DOORS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Minimum 32" clear opening	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
At least 18" clear floor space on pull side of door	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Closing speed minimum 3 seconds to within 3" of the latch	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Maximum pressure 5 pounds interior doors	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Threshold maximum ½" high, beveled on both sides	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Hardware operable with a closed fist (no conventional doorknobs or thumb latch devices)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Hardware minimum 36", maximum 48" above the floor	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Clear, level floor space extends out 5 ft from both sides of the door	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Door adjacent to revolving door is accessible and unlocked	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Doors opening into hazardous area have hardware that is knurled or roughened	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

RESTROOMS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
5 ft turning space measured 12" from the floor	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
AT LEAST ONE SINK			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Clear floor space of 30" by 48" to allow a forward approach	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Mounted without pedestal or legs, height 34" to top of rim	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Extends at least 22" from the wall	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Open knee space a minimum 19" deep, 30" width, and 27" high	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Cover exposed pipes with insulation	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Faucets operable with closed fist (lever or spring activated handle)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
AT LEAST ONE STALL			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Accessible to person using wheelchair at 60" wide by 72" deep	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Stall door is 36" wide	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Stall door swings out	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Stall door is self closing	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Stall door has a pull latch	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Lock on stall door is operable with a closed fist, and 32" above the floor	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Coat hook is 54" high	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	no coat hook
TOILET			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
18" from center to nearest side wall	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
42" minimum clear space from center to farthest wall or fixture	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Top of seat 17"-19" above the floor	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
GRAB BARS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
On back and side wall closest to toilet	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
1¼" diameter	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
1½" clearance to wall	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Located 30" above and parallel to the floor	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Acid-etched or roughened grab bar surface	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
42" long grab bars	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

RESTROOMS			
FIXTURES			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Toilet paper dispenser is 24" above floor	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
One mirror set a maximum 38" to bottom (if tilted, 42")	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Dispensers (towel, soap, etc.) at least one of each a maximum 42" above the floor	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

FLOORS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Non-slip surface	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Carpeting is high-density, low pile, non-absorbent, stretched taut, securely anchored	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Corridor width minimum is 3 ft	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Objects (signs, ceiling lights, fixtures) can only protrude 4" into the path of travel from a height of 27" to 80" above the floor	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

DRINKING FOUNTAINS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Spouts no higher than 36" from floor to outlet	<input type="checkbox"/>	<input type="checkbox"/>	
Hand operated push button or level controls	<input type="checkbox"/>	<input type="checkbox"/>	
Spouts located near front with stream of water as parallel to front as possible	<input type="checkbox"/>	<input type="checkbox"/>	N/A
If recessed, recess a minimum 30" width, and no deeper than depth of fountain	<input type="checkbox"/>	<input type="checkbox"/>	
If no clear knee space underneath, clear floor space 30" x 48" to allow parallel approach	<input type="checkbox"/>	<input type="checkbox"/>	

TELEPHONES			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Highest operating part a maximum 54" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
Access within 12" of phone, 30" high by 30" wide	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Adjustable volume control on headset so identified	<input type="checkbox"/>	<input type="checkbox"/>	

SIGNALS, OUTLETS, AND SWITCHES			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Switches and controls for light, heat, ventilation, windows, fire alarms, thermostats, etc., must be a minimum of 36" and a maximum of 48" above the floor for a forward reach, a maximum of 54" for a side reach	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Electrical outlets centered no lower than 18" above the floor	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Warning signals must be visual as well as audible	<input type="checkbox"/>	<input checked="" type="checkbox"/>	

SIGNS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Mounting height must be 60" to centerline of the sign	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Within 18" of door jamb or recessed	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Letters and numbers at least 1/4" high	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Letters and numbers raised .03"	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Letters and numbers contrast with the background color	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

SWIMMING POOLS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Ramp at least 34" wide with a non-slip surface extending into the shallow end, slope not exceeding 1:6 with handrails on both sides	<input type="checkbox"/>	<input type="checkbox"/>	<i>Note: Pools may accommodate either ramp or lifting access.</i>
Lifting device	<input type="checkbox"/>	<input type="checkbox"/>	<i>Note: Pools may accommodate either ramp or lifting access.</i>
Transfer area 18" above the path of travel and a minimum of 18" wide	<input type="checkbox"/>	<input type="checkbox"/>	
Unobstructed path of travel not less than 48" wide around pool	<input type="checkbox"/>	<input type="checkbox"/>	
Non-slip surface	<input type="checkbox"/>	<input type="checkbox"/>	

SHOWER ROOMS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Stalls 36" by 60" minimum, with a 36" door opening	<input type="checkbox"/>	<input type="checkbox"/>	<i>Note: Showers must accommodate both wheel-in and transfer use</i>
Floors are pitched to drain the stall at the corner farthest from entrance	<input type="checkbox"/>	<input type="checkbox"/>	
Floors are non-slip surface	<input type="checkbox"/>	<input type="checkbox"/>	
Controls operate by a single lever with a pressure balance mixing valve	<input type="checkbox"/>	<input type="checkbox"/>	

Controls are located on the center wall adjacent to the hinged seat	<input type="checkbox"/>	<input type="checkbox"/>	
Shower heads attached to a flexible metal hose	<input type="checkbox"/>	<input type="checkbox"/>	
Shower heads attached to wall mounting adjustable from 42" to 72" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
Seat is hinged and padded and at least 16" deep, folds upward, securely attached to side wall, height is 18" to the top of the seat, and at least 24" long	<input type="checkbox"/>	<input type="checkbox"/>	
Soap trays without handhold features unless they can support 250 pounds	<input type="checkbox"/>	<input type="checkbox"/>	N/A
2 grab bars are provided, one 30" and one 48" long, or one continuous L shaped bar	<input type="checkbox"/>	<input type="checkbox"/>	
Grab bars are placed horizontally at 36" above the floor line	<input type="checkbox"/>	<input type="checkbox"/>	

PICNICKING			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
A minimum of 5% of the total tables must be accessible with clear space under the tabletop not less than 30" wide and 19" deep per seating space and not less than 27" clear from the ground to the underside of the table. An additional 29" clear space (totaling 48") must extend beyond the 19" clear space under the table to provide access	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
For tables without toe clearance, the knee space under the table must be at least 28" high, 30" wide and 24" deep.	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Top of table no higher than 32" above ground	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Surface of the clear ground space under and around the table must be stable, firm and slip-resistant, and evenly graded with a maximum slope of 2% in all directions	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Accessible tables, grills and fire rings must have clear ground space of at least 36" around the perimeter	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

ADA FACILITY INVENTORY

LOCATION: *Mason Fields*

ACTIVITY	EQUIPMENT	NOTES	
Picnic Facilities	Tables & Benches	<input checked="" type="checkbox"/> Located adjacent to accessible paths	
		<input type="checkbox"/> Access to Open Spaces	
		<input checked="" type="checkbox"/> Back and Arm Rests	
		<input checked="" type="checkbox"/> Adequate number	
	Grills	<input type="checkbox"/> Height of Cooking Surface	<i>NIA</i>
		<input type="checkbox"/> Located adjacent to accessible paths	
	Trash Cans	<input checked="" type="checkbox"/> Located adjacent to accessible paths	
Picnic Shelters	<input type="checkbox"/> Located adjacent to accessible paths	<i>NIA</i>	
	<input type="checkbox"/> Located near accessible infrastructure and amenities	<i>NIA</i>	
Trails		<input type="checkbox"/> Surface material	
		<input type="checkbox"/> Dimensions	<i>NIA</i>
		<input type="checkbox"/> Rails	
		<input type="checkbox"/> Accessible signage	
Swimming Facilities	Pools	<input type="checkbox"/> Entrance	<i>NIA</i>
		<input type="checkbox"/> Location from accessible parking	<i>NIA</i>
		<input type="checkbox"/> Safety features	
	Beaches	<input type="checkbox"/> Location from accessible path into water	<i>NIA</i>
		<input type="checkbox"/> Handrails	<i>NIA</i>
		<input type="checkbox"/> Location from accessible parking	<i>NIA</i>
	<input type="checkbox"/> Shade provided		
Play Areas	Play Equipment	<input checked="" type="checkbox"/> Same experience provided to all	
	Access Routes	<input checked="" type="checkbox"/> Located adjacent to accessible paths	
		<input checked="" type="checkbox"/> Enough space between equipment for wheelchair	
Game Areas	Access Routes	<input checked="" type="checkbox"/> Located adjacent to accessible paths	
		<input checked="" type="checkbox"/> Berm cuts onto courts	
	Equipment	<input checked="" type="checkbox"/> Height	
		<input checked="" type="checkbox"/> Dimensions	
	<input checked="" type="checkbox"/> Spectator Seating		

Mason Fields

Boat Docks	Access Routes	<input type="checkbox"/> Located adjacent to accessible paths	NA
		<input type="checkbox"/> Handrails	
Fishing Facilities	Access Routes	<input type="checkbox"/> Located adjacent to accessible paths	N/A
		<input type="checkbox"/> Handrails	
	Equipment	<input type="checkbox"/> Arm Rests	
		<input type="checkbox"/> Bait Shelves	
		<input type="checkbox"/> Handrails	
<input type="checkbox"/> Fish Cleaning Tables			
Programming	<input type="checkbox"/> Learn-to-Swim	N/A	
	<input type="checkbox"/> Guided Hikes		
	<input type="checkbox"/> Interpretive Programs		
Services	<input type="checkbox"/> Information available in alternative formats	N/A	
	<input type="checkbox"/> Process to request interpretive services		

Mason Fields

PARKING			
TOTAL SPACES		REQUIRED ACCESSIBLE SPACES	
Up to 25	<input type="checkbox"/>	1 space	
26-50	<input type="checkbox"/>	2 spaces	
51-75	<input checked="" type="checkbox"/>	3 spaces	
76-100	<input type="checkbox"/>	4 spaces	
101-150	<input type="checkbox"/>	5 spaces	
151-200	<input type="checkbox"/>	6 spaces	
201-300	<input type="checkbox"/>	7 spaces	
301-400	<input type="checkbox"/>	8 spaces	
401-500	<input type="checkbox"/>	9 spaces	
ACCESSIBLE SPACE SPECIFICATIONS	YES	NO	COMMENTS/TRANSITION NOTES
Accessible space located closest to accessible entrance	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Where spaces cannot be located within 200 ft of accessible entrance, drop-off area is provided within 100 ft.	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Minimum width of 13 ft includes 8 ft space plus 5 ft access aisle	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Van space – minimum of 1 van space for every accessible space, 8 ft wide plus 8 ft aisle. Alternative is to make all accessible spaces 11 ft wide with 5 ft aisle.	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Sign with international symbol of accessibility at each space or pair of spaces	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Sign minimum 5 ft, maximum 8 ft to top of sign	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Surface evenly paved or hard-packed (no cracks)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Surface slope less than 1:20, 5%	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Curbcut to pathway from parking lot at each space or pair of spaces, if sidewalk (curb) is present	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Curbcut is a minimum width of 3 ft, excluding sloped sides, has sloped sides, all slopes not to exceed 1:12, and textured or painted yellow	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

Mason Fields

RAMPS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Slope Maximum 1:12	<input type="checkbox"/>	<input type="checkbox"/>	
Minimum width 4 ft between handrails	<input type="checkbox"/>	<input type="checkbox"/>	
Handrails on both sides if ramp is longer than 6 ft	<input type="checkbox"/>	<input type="checkbox"/>	
Handrails at 34" and 19" from ramp surface	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Handrails extend 12" beyond top and bottom	<input type="checkbox"/>	<input type="checkbox"/>	
Handgrip oval or round	<input type="checkbox"/>	<input type="checkbox"/>	
Handgrip smooth surface	<input type="checkbox"/>	<input type="checkbox"/>	
Handgrip diameter between 1¼" and 2"	<input type="checkbox"/>	<input type="checkbox"/>	
Clearance of 1½" between wall and wall rail	<input type="checkbox"/>	<input type="checkbox"/>	
Non-slip surface	<input type="checkbox"/>	<input type="checkbox"/>	
Level platforms (4ft x 4 ft) at every 30 ft, at top, at bottom, at change of direction	<input type="checkbox"/>	<input type="checkbox"/>	

SITE ACCESS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Accessible path of travel from passenger disembarking area and parking area to accessible entrance	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Disembarking area at accessible entrance	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Surface evenly paved or hard-packed	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
No ponding of water	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

PATH OF TRAVEL			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Path does not require the use of stairs	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Path is stable, firm and slip resistant	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
3 ft wide minimum	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Slope maximum 1:20 (5%) and maximum cross pitch is 2% (1:50).	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Continuous common surface, no changes in level greater than ½ inch	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Any objects protruding onto the pathway must be detected by a person with a visual disability using a cane	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

Mason Fields

PATH OF TRAVEL			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Objects protruding more than 4" from the wall must be within 27" of the ground, or higher than 80"	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Curb on the pathway must have curb cuts at drives, parking and drop-offs	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

ENTRANCES			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Primary public entrances accessible to person using wheelchair, must be signed, gotten to independently, and <i>not</i> be the service entrance	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Level space extending 5 ft. from the door, interior and exterior of entrance doors	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Minimum 32" clear width opening (i.e. 36" door with standard hinge)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
At least 18" clear floor area on latch, pull side of door	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Door handle no higher than 48" and operable with a closed fist	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Vestibule is 4 ft plus the width of the door swinging into the space	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Entrance(s) on a level that makes elevators accessible	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Door mats less than 1/2" thick are securely fastened	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Door mats more than 1/2" thick are recessed	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Grates in path of travel have openings of 1/2" maximum	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Signs at non-accessible entrance(s) indicate direction to accessible entrance	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Emergency egress – alarms with flashing lights and audible signals, sufficiently lighted	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

Mason Fields

STAIRS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
No open risers	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Nosings not projecting	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Treads no less than 11" wide	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Handrails on both sides	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Handrails 34"-38" above tread	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Handrail extends a minimum of 1 ft beyond top and bottom riser (if no safety hazard and space permits)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Handgrip oval or round	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Handgrip has a smooth surface	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Handgrip diameter between 1¼" and 1½"	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
1½" clearance between wall and handrail	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

DOORS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Minimum 32" clear opening	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
At least 18" clear floor space on pull side of door	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Closing speed minimum 3 seconds to within 3" of the latch	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Maximum pressure 5 pounds interior doors	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Threshold maximum ½" high, beveled on both sides	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Hardware operable with a closed fist (no conventional doorknobs or thumb latch devices)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Hardware minimum 36", maximum 48" above the floor	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Clear, level floor space extends out 5 ft from both sides of the door	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Door adjacent to revolving door is accessible and unlocked	<input type="checkbox"/>	<input type="checkbox"/>	NA
Doors opening into hazardous area have hardware that is knurled or roughened	<input type="checkbox"/>	<input type="checkbox"/>	NA

Maxon Fields

RESTROOMS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
5 ft turning space measured 12" from the floor	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
AT LEAST ONE SINK			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Clear floor space of 30" by 48" to allow a forward approach	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Mounted without pedestal or legs, height 34" to top of rim	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Extends at least 22" from the wall	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Open knee space a minimum 19" deep, 30" width, and 27" high	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Cover exposed pipes with insulation	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Faucets operable with closed fist (lever or spring activated handle)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
AT LEAST ONE STALL			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Accessible to person using wheelchair at 60" wide by 72" deep	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Stall door is 36" wide	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Stall door swings out	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Stall door is self closing	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Stall door has a pull latch	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Lock on stall door is operable with a closed fist, and 32" above the floor	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Coat hook is 54" high	<input type="checkbox"/>	<input type="checkbox"/>	N/A
TOILET			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
18" from center to nearest side wall	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
42" minimum clear space from center to farthest wall or fixture	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Top of seat 17"-19" above the floor	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
GRAB BARS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
On back and side wall closest to toilet	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
1¼" diameter	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
1½" clearance to wall	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Located 30" above and parallel to the floor	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Acid-etched or roughened grab bar surface	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
42" long grab bars	<input type="checkbox"/>	<input checked="" type="checkbox"/>	

Mason Fields

RESTROOMS			
FIXTURES			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Toilet paper dispenser is 24" above floor	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
One mirror set a maximum 38" to bottom (if tilted, 42")	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Dispensers (towel, soap, etc.) at least one of each a maximum 42" above the floor	<input type="checkbox"/>	<input checked="" type="checkbox"/>	

FLOORS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Non-slip surface	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Carpeting is high-density, low pile, non-absorbent, stretched taut, securely anchored	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Corridor width minimum is 3 ft	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Objects (signs, ceiling lights, fixtures) can only protrude 4" into the path of travel from a height of 27" to 80" above the floor	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

DRINKING FOUNTAINS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Spouts no higher than 36" from floor to outlet	<input type="checkbox"/>	<input type="checkbox"/>	
Hand operated push button or level controls	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Spouts located near front with stream of water as parallel to front as possible	<input type="checkbox"/>	<input type="checkbox"/>	N/A
If recessed, recess a minimum 30" width, and no deeper than depth of fountain	<input type="checkbox"/>	<input type="checkbox"/>	N/A
If no clear knee space underneath, clear floor space 30" x 48" to allow parallel approach	<input type="checkbox"/>	<input type="checkbox"/>	N/A

TELEPHONES			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Highest operating part a maximum 54" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Access within 12" of phone, 30" high by 30" wide	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Adjustable volume control on headset so identified	<input type="checkbox"/>	<input type="checkbox"/>	N/A

Mason Fields

SIGNALS, OUTLETS, AND SWITCHES			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Switches and controls for light, heat, ventilation, windows, fire alarms, thermostats, etc., must be a minimum of 36" and a maximum of 48" above the floor for a forward reach, a maximum of 54" for a side reach	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Electrical outlets centered no lower than 18" above the floor	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Warning signals must be visual as well as audible	<input type="checkbox"/>	<input checked="" type="checkbox"/>	

SIGNS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Mounting height must be 60" to centerline of the sign	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Within 18" of door jamb or recessed	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Letters and numbers at least 1 1/4" high	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Letters and numbers raised .03"	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Letters and numbers contrast with the background color	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

SWIMMING POOLS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Ramp at least 34" wide with a non-slip surface extending into the shallow end, slope not exceeding 1:6 with handrails on both sides	<input type="checkbox"/>	<input type="checkbox"/>	Note: Pools may accommodate either ramp or lifting access.
Lifting device	<input type="checkbox"/>	<input type="checkbox"/>	Note: Pools may accommodate either ramp or lifting access.
Transfer area 18" above the path of travel and a minimum of 18" wide	<input type="checkbox"/>	<input type="checkbox"/>	
Unobstructed path of travel not less than 48" wide around pool	<input type="checkbox"/>	<input type="checkbox"/>	
Non-slip surface	<input type="checkbox"/>	<input type="checkbox"/>	

SHOWER ROOMS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Stalls 36" by 60" minimum, with a 36" door opening	<input type="checkbox"/>	<input type="checkbox"/>	Note: Showers must accommodate both wheel-in and transfer use
Floors are pitched to drain the stall at the corner farthest from entrance	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Floors are non-slip surface	<input type="checkbox"/>	<input type="checkbox"/>	
Controls operate by a single lever with a pressure balance mixing valve	<input type="checkbox"/>	<input type="checkbox"/>	

Mason Fields

Controls are located on the center wall adjacent to the hinged seat	<input type="checkbox"/>	<input type="checkbox"/>	
Shower heads attached to a flexible metal hose	<input type="checkbox"/>	<input type="checkbox"/>	
Shower heads attached to wall mounting adjustable from 42" to 72" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
Seat is hinged and padded and at least 16" deep, folds upward, securely attached to side wall, height is 18" to the top of the seat, and at least 24" long	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Soap trays without handhold features unless they can support 250 pounds	<input type="checkbox"/>	<input type="checkbox"/>	
2 grab bars are provided, one 30" and one 48" long, or one continuous L shaped bar	<input type="checkbox"/>	<input type="checkbox"/>	
Grab bars are placed horizontally at 36" above the floor line	<input type="checkbox"/>	<input type="checkbox"/>	

PICNICKING			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
A minimum of 5% of the total tables must be accessible with clear space under the tabletop not less than 30" wide and 19" deep per seating space and not less than 27" clear from the ground to the underside of the table. An additional 29" clear space (totaling 48") must extend beyond the 19" clear space under the table to provide access	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
For tables without toe clearance, the knee space under the table must be at least 28" high, 30" wide and 24" deep.	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Top of table no higher than 32" above ground	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Surface of the clear ground space under and around the table must be stable, firm and slip-resistant, and evenly graded with a maximum slope of 2% in all directions	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Accessible tables, grills and fire rings must have clear ground space of at least 36" around the perimeter	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

ADA FACILITY INVENTORY

LOCATION: *Ruth Rhind Field*

ACTIVITY	EQUIPMENT	NOTES
Picnic Facilities	Tables & Benches	<input checked="" type="checkbox"/> Located adjacent to accessible paths
		<input checked="" type="checkbox"/> Access to Open Spaces
		<input type="checkbox"/> Back and Arm Rests
		<input checked="" type="checkbox"/> Adequate number
	Grills	<input type="checkbox"/> Height of Cooking Surface
		<input type="checkbox"/> Located adjacent to accessible paths <i>NIA</i>
Trash Cans	<input checked="" type="checkbox"/> Located adjacent to accessible paths	
Picnic Shelters	<input type="checkbox"/> Located adjacent to accessible paths	
	<input type="checkbox"/> Located near accessible infrastructure and amenities <i>NIA</i>	
Trails		<input checked="" type="checkbox"/> Surface material <i>wood chips & gravel</i>
		<input checked="" type="checkbox"/> Dimensions <i>10ft wide - 2 miles long</i>
		<input type="checkbox"/> Rails <i>NIA</i>
		<input type="checkbox"/> Accessible signage
Swimming Facilities	Pools	<input type="checkbox"/> Entrance
		<input type="checkbox"/> Location from accessible parking <i>NIA</i>
		<input type="checkbox"/> Safety features
	Beaches	<input type="checkbox"/> Location from accessible path into water
		<input type="checkbox"/> Handrails
		<input type="checkbox"/> Location from accessible parking <i>NIA</i>
	<input type="checkbox"/> Shade provided	
Play Areas	Play Equipment	<input checked="" type="checkbox"/> Same experience provided to all
	Access Routes	<input checked="" type="checkbox"/> Located adjacent to accessible paths
		<input checked="" type="checkbox"/> Enough space between equipment for wheelchair
Game Areas	Access Routes	<input checked="" type="checkbox"/> Located adjacent to accessible paths
		<input checked="" type="checkbox"/> Berm cuts onto courts
	Equipment	<input checked="" type="checkbox"/> Height
		<input checked="" type="checkbox"/> Dimensions
	<input checked="" type="checkbox"/> Spectator Seating	

Boat Docks	Access Routes	<input type="checkbox"/> Located adjacent to accessible paths	N/A
		<input type="checkbox"/> Handrails	
Fishing Facilities	Access Routes	<input type="checkbox"/> Located adjacent to accessible paths	N/A
		<input type="checkbox"/> Handrails	
	Equipment	<input type="checkbox"/> Arm Rests	
		<input type="checkbox"/> Bait Shelves	
		<input type="checkbox"/> Handrails	
<input type="checkbox"/> Fish Cleaning Tables			
Programming	<input type="checkbox"/> Learn-to-Swim	N/A	
	<input type="checkbox"/> Guided Hikes		
	<input type="checkbox"/> Interpretive Programs		
Services	<input type="checkbox"/> Information available in alternative formats	N/A	
	<input type="checkbox"/> Process to request interpretive services		

PARKING			
TOTAL SPACES		REQUIRED ACCESSIBLE SPACES	
Up to 25	<input type="checkbox"/>	1 space	
26-50	<input checked="" type="checkbox"/>	2 spaces	
51-75	<input type="checkbox"/>	3 spaces	
76-100	<input type="checkbox"/>	4 spaces	
101-150	<input type="checkbox"/>	5 spaces	
151-200	<input type="checkbox"/>	6 spaces	
201-300	<input type="checkbox"/>	7 spaces	
301-400	<input type="checkbox"/>	8 spaces	
401-500	<input type="checkbox"/>	9 spaces	
ACCESSIBLE SPACE SPECIFICATIONS	YES	NO	COMMENTS/TRANSITION NOTES
Accessible space located closest to accessible entrance	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Where spaces cannot be located within 200 ft of accessible entrance, drop-off area is provided within 100 ft.	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Minimum width of 13 ft includes 8 ft space plus 5 ft access aisle	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Van space – minimum of 1 van space for every accessible space, 8 ft wide plus 8 ft aisle. Alternative is to make all accessible spaces 11 ft wide with 5 ft aisle.	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Sign with international symbol of accessibility at each space or pair of spaces	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Sign minimum 5 ft, maximum 8 ft to top of sign	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Surface evenly paved or hard-packed (no cracks)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Surface slope less than 1:20, 5%	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Curbside to pathway from parking lot at each space or pair of spaces, if sidewalk (curb) is present	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Curbside is a minimum width of 3 ft, excluding sloped sides, has sloped sides, all slopes not to exceed 1:12, and textured or painted yellow	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

RAMPS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Slope Maximum 1:12	<input type="checkbox"/>	<input checked="" type="checkbox"/>	N/A
Minimum width 4 ft between handrails	<input type="checkbox"/>	<input checked="" type="checkbox"/>	N/A
Handrails on both sides if ramp is longer than 6 ft	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Handrails at 34" and 19" from ramp surface	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Handrails extend 12" beyond top and bottom	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Handgrip oval or round	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Handgrip smooth surface	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Handgrip diameter between 1¼" and 2"	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Clearance of 1½" between wall and wall rail	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Non-slip surface	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Level platforms (4ft x 4 ft) at every 30 ft, at top, at bottom, at change of direction	<input type="checkbox"/>	<input type="checkbox"/>	N/A

SITE ACCESS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Accessible path of travel from passenger disembarking area and parking area to accessible entrance	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Disembarking area at accessible entrance	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Surface evenly paved or hard-packed	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
No ponding of water	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

PATH OF TRAVEL			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Path does not require the use of stairs	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Path is stable, firm and slip resistant	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
3 ft wide minimum	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Slope maximum 1:20 (5%) and maximum cross pitch is 2% (1:50).	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Continuous common surface, no changes in level greater than ½ inch	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Any objects protruding onto the pathway must be detected by a person with a visual disability using a cane	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

PATH OF TRAVEL			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Objects protruding more than 4" from the wall must be within 27" of the ground, or higher than 80"	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Curb on the pathway must have curb cuts at drives, parking and drop-offs	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

ENTRANCES			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Primary public entrances accessible to person using wheelchair, must be signed, gotten to independently, and <i>not</i> be the service entrance	<input type="checkbox"/>	<input type="checkbox"/>	no indoor
Level space extending 5 ft. from the door, interior and exterior of entrance doors	<input type="checkbox"/>	<input type="checkbox"/>	spaces
Minimum 32" clear width opening (i.e. 36" door with standard hinge)	<input type="checkbox"/>	<input type="checkbox"/>	N/A
At least 18" clear floor area on latch, pull side of door	<input type="checkbox"/>	<input type="checkbox"/>	
Door handle no higher than 48" and operable with a closed fist	<input type="checkbox"/>	<input type="checkbox"/>	
Vestibule is 4 ft plus the width of the door swinging into the space	<input type="checkbox"/>	<input type="checkbox"/>	
Entrance(s) on a level that makes elevators accessible	<input type="checkbox"/>	<input type="checkbox"/>	
Door mats less than 1/2" thick are securely fastened	<input type="checkbox"/>	<input type="checkbox"/>	
Door mats more than 1/2" thick are recessed	<input type="checkbox"/>	<input type="checkbox"/>	
Grates in path of travel have openings of 1/2" maximum	<input type="checkbox"/>	<input type="checkbox"/>	
Signs at non-accessible entrance(s) indicate direction to accessible entrance	<input type="checkbox"/>	<input type="checkbox"/>	
Emergency egress – alarms with flashing lights and audible signals, sufficiently lighted	<input type="checkbox"/>	<input type="checkbox"/>	

STAIRS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
No open risers	<input type="checkbox"/>	<input type="checkbox"/>	
Nosings not projecting	<input type="checkbox"/>	<input type="checkbox"/>	
Treads no less than 11" wide	<input type="checkbox"/>	<input type="checkbox"/>	
Handrails on both sides	<input type="checkbox"/>	<input type="checkbox"/>	
Handrails 34"-38" above tread	<input type="checkbox"/>	<input type="checkbox"/>	
Handrail extends a minimum of 1 ft beyond top and bottom riser (if no safety hazard and space permits)	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Handgrip oval or round	<input type="checkbox"/>	<input type="checkbox"/>	
Handgrip has a smooth surface	<input type="checkbox"/>	<input type="checkbox"/>	
Handgrip diameter between 1¼" and 1½"	<input type="checkbox"/>	<input type="checkbox"/>	
1½" clearance between wall and handrail	<input type="checkbox"/>	<input type="checkbox"/>	

DOORS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Minimum 32" clear opening	<input type="checkbox"/>	<input type="checkbox"/>	
At least 18" clear floor space on pull side of door	<input type="checkbox"/>	<input type="checkbox"/>	
Closing speed minimum 3 seconds to within 3" of the latch	<input type="checkbox"/>	<input type="checkbox"/>	
Maximum pressure 5 pounds interior doors	<input type="checkbox"/>	<input type="checkbox"/>	
Threshold maximum ½" high, beveled on both sides	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Hardware operable with a closed fist (no conventional doorknobs or thumb latch devices)	<input type="checkbox"/>	<input type="checkbox"/>	
Hardware minimum 36", maximum 48" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
Clear, level floor space extends out 5 ft from both sides of the door	<input type="checkbox"/>	<input type="checkbox"/>	
Door adjacent to revolving door is accessible and unlocked	<input type="checkbox"/>	<input type="checkbox"/>	
Doors opening into hazardous area have hardware that is knurled or roughened	<input type="checkbox"/>	<input type="checkbox"/>	

RESTROOMS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
5 ft turning space measured 12" from the floor	<input type="checkbox"/>	<input type="checkbox"/>	N/A Portajohn
AT LEAST ONE SINK			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Clear floor space of 30" by 48" to allow a forward approach	<input type="checkbox"/>	<input type="checkbox"/>	
Mounted without pedestal or legs, height 34" to top of rim	<input type="checkbox"/>	<input type="checkbox"/>	
Extends at least 22" from the wall	<input type="checkbox"/>	<input type="checkbox"/>	
Open knee space a minimum 19" deep, 30" width, and 27" high	<input type="checkbox"/>	<input type="checkbox"/>	
Cover exposed pipes with insulation	<input type="checkbox"/>	<input type="checkbox"/>	
Faucets operable with closed fist (lever or spring activated handle)	<input type="checkbox"/>	<input type="checkbox"/>	
AT LEAST ONE STALL			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Accessible to person using wheelchair at 60" wide by 72" deep	<input type="checkbox"/>	<input type="checkbox"/>	
Stall door is 36" wide	<input type="checkbox"/>	<input type="checkbox"/>	
Stall door swings out	<input type="checkbox"/>	<input type="checkbox"/>	
Stall door is self closing	<input type="checkbox"/>	<input type="checkbox"/>	
Stall door has a pull latch	<input type="checkbox"/>	<input type="checkbox"/>	
Lock on stall door is operable with a closed fist, and 32" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
Coat hook is 54" high	<input type="checkbox"/>	<input type="checkbox"/>	
TOILET			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
18" from center to nearest side wall	<input type="checkbox"/>	<input type="checkbox"/>	
42" minimum clear space from center to farthest wall or fixture	<input type="checkbox"/>	<input type="checkbox"/>	
Top of seat 17"-19" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
GRAB BARS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
On back and side wall closest to toilet	<input type="checkbox"/>	<input type="checkbox"/>	
1¼" diameter	<input type="checkbox"/>	<input type="checkbox"/>	
1½" clearance to wall	<input type="checkbox"/>	<input type="checkbox"/>	
Located 30" above and parallel to the floor	<input type="checkbox"/>	<input type="checkbox"/>	
Acid-etched or roughened grab bar surface	<input type="checkbox"/>	<input type="checkbox"/>	
42" long grab bars	<input type="checkbox"/>	<input type="checkbox"/>	

RESTROOMS			
FIXTURES			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Toilet paper dispenser is 24" above floor	<input type="checkbox"/>	<input type="checkbox"/>	N/A
One mirror set a maximum 38" to bottom (if tilted, 42")	<input type="checkbox"/>	<input type="checkbox"/>	
Dispensers (towel, soap, etc.) at least one of each a maximum 42" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	

FLOORS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Non-slip surface	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Carpeting is high-density, low pile, non-absorbent, stretched taut, securely anchored	<input type="checkbox"/>	<input type="checkbox"/>	
Corridor width minimum is 3 ft	<input type="checkbox"/>	<input type="checkbox"/>	
Objects (signs, ceiling lights, fixtures) can only protrude 4" into the path of travel from a height of 27" to 80" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	

DRINKING FOUNTAINS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Spouts no higher than 36" from floor to outlet	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Hand operated push button or level controls	<input type="checkbox"/>	<input type="checkbox"/>	
Spouts located near front with stream of water as parallel to front as possible	<input type="checkbox"/>	<input type="checkbox"/>	
If recessed, recess a minimum 30" width, and no deeper than depth of fountain	<input type="checkbox"/>	<input type="checkbox"/>	
If no clear knee space underneath, clear floor space 30" x 48" to allow parallel approach	<input type="checkbox"/>	<input type="checkbox"/>	

TELEPHONES			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Highest operating part a maximum 54" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Access within 12" of phone, 30" high by 30" wide	<input type="checkbox"/>	<input type="checkbox"/>	
Adjustable volume control on headset so identified	<input type="checkbox"/>	<input type="checkbox"/>	

SIGNALS, OUTLETS, AND SWITCHES			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Switches and controls for light, heat, ventilation, windows, fire alarms, thermostats, etc., must be a minimum of 36" and a maximum of 48" above the floor for a forward reach, a maximum of 54" for a side reach	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Electrical outlets centered no lower than 18" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
Warning signals must be visual as well as audible	<input type="checkbox"/>	<input type="checkbox"/>	

SIGNS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Mounting height must be 60" to centerline of the sign	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Within 18" of door jamb or recessed	<input type="checkbox"/>	<input type="checkbox"/>	
Letters and numbers at least 1¼" high	<input type="checkbox"/>	<input type="checkbox"/>	
Letters and numbers raised .03"	<input type="checkbox"/>	<input type="checkbox"/>	
Letters and numbers contrast with the background color	<input type="checkbox"/>	<input type="checkbox"/>	

SWIMMING POOLS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Ramp at least 34" wide with a non-slip surface extending into the shallow end, slope not exceeding 1:6 with handrails on both sides	<input type="checkbox"/>	<input type="checkbox"/>	<i>Note: Pools may accommodate either ramp or lifting access.</i>
Lifting device	<input type="checkbox"/>	<input type="checkbox"/>	<i>Note: Pools may accommodate either ramp or lifting access.</i>
Transfer area 18" above the path of travel and a minimum of 18" wide	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Unobstructed path of travel not less than 48" wide around pool	<input type="checkbox"/>	<input type="checkbox"/>	
Non-slip surface	<input type="checkbox"/>	<input type="checkbox"/>	

SHOWER ROOMS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Stalls 36" by 60" minimum, with a 36" door opening	<input type="checkbox"/>	<input type="checkbox"/>	<i>Note: Showers must accommodate both wheel-in and transfer use</i>
Floors are pitched to drain the stall at the corner farthest from entrance	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Floors are non-slip surface	<input type="checkbox"/>	<input type="checkbox"/>	
Controls operate by a single lever with a pressure balance mixing valve	<input type="checkbox"/>	<input type="checkbox"/>	

Controls are located on the center wall adjacent to the hinged seat	<input type="checkbox"/>	<input type="checkbox"/>	
Shower heads attached to a flexible metal hose	<input type="checkbox"/>	<input type="checkbox"/>	
Shower heads attached to wall mounting adjustable from 42" to 72" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
Seat is hinged and padded and at least 16" deep, folds upward, securely attached to side wall, height is 18" to the top of the seat, and at least 24" long	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Soap trays without handhold features unless they can support 250 pounds	<input type="checkbox"/>	<input type="checkbox"/>	
2 grab bars are provided, one 30" and one 48" long, or one continuous L shaped bar	<input type="checkbox"/>	<input type="checkbox"/>	
Grab bars are placed horizontally at 36" above the floor line	<input type="checkbox"/>	<input type="checkbox"/>	

PICNICKING			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
A minimum of 5% of the total tables must be accessible with clear space under the tabletop not less than 30" wide and 19" deep per seating space and not less than 27" clear from the ground to the underside of the table. An additional 29" clear space (totaling 48") must extend beyond the 19" clear space under the table to provide access	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
For tables without toe clearance, the knee space under the table must be at least 28" high, 30" wide and 24" deep.	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Top of table no higher than 32" above ground	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Surface of the clear ground space under and around the table must be stable, firm and slip-resistant, and evenly graded with a maximum slope of 2% in all directions	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Accessible tables, grills and fire rings must have clear ground space of at least 36" around the perimeter	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

ADA FACILITY INVENTORY

LOCATION: Town Forest / Dog Park

ACTIVITY	EQUIPMENT	NOTES
Picnic Facilities	Tables & Benches	<input checked="" type="checkbox"/> Located adjacent to accessible paths
		<input checked="" type="checkbox"/> Access to Open Spaces
		<input checked="" type="checkbox"/> Back and Arm Rests
		<input checked="" type="checkbox"/> Adequate number
	Grills	<input type="checkbox"/> Height of Cooking Surface
		<input type="checkbox"/> Located adjacent to accessible paths
Trash Cans	<input checked="" type="checkbox"/> Located adjacent to accessible paths	
Picnic Shelters	<input type="checkbox"/> Located adjacent to accessible paths	
	<input type="checkbox"/> Located near accessible infrastructure and amenities	
Trails		<input checked="" type="checkbox"/> Surface material
		<input checked="" type="checkbox"/> Dimensions
		<input checked="" type="checkbox"/> Rails
		<input checked="" type="checkbox"/> Accessible signage
Swimming Facilities	Pools	<input type="checkbox"/> Entrance
		<input type="checkbox"/> Location from accessible parking
		<input type="checkbox"/> Safety features
	Beaches	<input type="checkbox"/> Location from accessible path into water
		<input type="checkbox"/> Handrails
		<input type="checkbox"/> Location from accessible parking
Play Areas	Play Equipment	<input type="checkbox"/> Same experience provided to all
	Access Routes	<input type="checkbox"/> Located adjacent to accessible paths
		<input type="checkbox"/> Enough space between equipment for wheelchair
Game Areas	Access Routes	<input type="checkbox"/> Located adjacent to accessible paths
		<input type="checkbox"/> Berm cuts onto courts
	Equipment	<input type="checkbox"/> Height
		<input type="checkbox"/> Dimensions
	<input type="checkbox"/> Spectator Seating	

N/A

N/A

N/A

N/A

N/A

N/A

N/A

N/A

Boat Docks	Access Routes	<input type="checkbox"/> Located adjacent to accessible paths	N/A
		<input type="checkbox"/> Handrails	
Fishing Facilities	Access Routes	<input type="checkbox"/> Located adjacent to accessible paths	N/A
		<input type="checkbox"/> Handrails	
	Equipment	<input type="checkbox"/> Arm Rests	
		<input type="checkbox"/> Bait Shelves	
		<input type="checkbox"/> Fish Cleaning Tables	
Programming	<input type="checkbox"/> Learn-to-Swim	N/A	
	<input type="checkbox"/> Guided Hikes		
	<input type="checkbox"/> Interpretive Programs		
Services	<input type="checkbox"/> Information available in alternative formats	N/A	
	<input type="checkbox"/> Process to request interpretive services		

PARKING			
TOTAL SPACES	REQUIRED ACCESSIBLE SPACES		
Up to 25	<input checked="" type="checkbox"/>		1 space
26-50	<input type="checkbox"/>		2 spaces
51-75	<input type="checkbox"/>		3 spaces
76-100	<input type="checkbox"/>		4 spaces
101-150	<input type="checkbox"/>		5 spaces
151-200	<input type="checkbox"/>		6 spaces
201-300	<input type="checkbox"/>		7 spaces
301-400	<input type="checkbox"/>		8 spaces
401-500	<input type="checkbox"/>		9 spaces
ACCESSIBLE SPACE SPECIFICATIONS	YES	NO	COMMENTS/TRANSITION NOTES
Accessible space located closest to accessible entrance	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Where spaces cannot be located within 200 ft of accessible entrance, drop-off area is provided within 100 ft.	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Minimum width of 13 ft includes 8 ft space plus 5 ft access aisle	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Van space – minimum of 1 van space for every accessible space, 8 ft wide plus 8 ft aisle. Alternative is to make all accessible spaces 11 ft wide with 5 ft aisle.	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Sign with international symbol of accessibility at each space or pair of spaces	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Sign minimum 5 ft, maximum 8 ft to top of sign	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Surface evenly paved or hard-packed (no cracks)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Surface slope less than 1:20, 5%	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Curbscut to pathway from parking lot at each space or pair of spaces, if sidewalk (curb) is present	<input type="checkbox"/>	<input type="checkbox"/>	no curbs
Curbscut is a minimum width of 3 ft, excluding sloped sides, has sloped sides, all slopes not to exceed 1:12, and textured or painted yellow	<input type="checkbox"/>	<input type="checkbox"/>	N/A

RAMPS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Slope Maximum 1:12	<input type="checkbox"/>	<input type="checkbox"/>	
Minimum width 4 ft between handrails	<input type="checkbox"/>	<input type="checkbox"/>	
Handrails on both sides if ramp is longer than 6 ft	<input type="checkbox"/>	<input type="checkbox"/>	
Handrails at 34" and 19" from ramp surface	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Handrails extend 12" beyond top and bottom	<input type="checkbox"/>	<input type="checkbox"/>	
Handgrip oval or round	<input type="checkbox"/>	<input type="checkbox"/>	
Handgrip smooth surface	<input type="checkbox"/>	<input type="checkbox"/>	
Handgrip diameter between 1¼" and 2"	<input type="checkbox"/>	<input type="checkbox"/>	
Clearance of 1½" between wall and wall rail	<input type="checkbox"/>	<input type="checkbox"/>	
Non-slip surface	<input type="checkbox"/>	<input type="checkbox"/>	
Level platforms (4ft x 4 ft) at every 30 ft, at top, at bottom, at change of direction	<input type="checkbox"/>	<input type="checkbox"/>	

SITE ACCESS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Accessible path of travel from passenger disembarking area and parking area to accessible entrance	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Disembarking area at accessible entrance	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Surface evenly paved or hard-packed	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
No ponding of water	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

PATH OF TRAVEL			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Path does not require the use of stairs	<input type="checkbox"/>	<input type="checkbox"/>	No Stair
Path is stable, firm and slip resistant	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
3 ft wide minimum	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Slope maximum 1:20 (5%) and maximum cross pitch is 2% (1:50).	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Continuous common surface, no changes in level greater than ½ inch	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Any objects protruding onto the pathway must be detected by a person with a visual disability using a cane	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

PATH OF TRAVEL			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Objects protruding more than 4" from the wall must be within 27" of the ground, or higher than 80"	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Curb on the pathway must have curb cuts at drives, parking and drop-offs	<input type="checkbox"/>	<input type="checkbox"/>	no curbs

ENTRANCES			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Primary public entrances accessible to person using wheelchair, must be signed, gotten to independently, and <i>not</i> be the service entrance	<input type="checkbox"/>	<input type="checkbox"/>	
Level space extending 5 ft. from the door, interior and exterior of entrance doors	<input type="checkbox"/>	<input type="checkbox"/>	
Minimum 32" clear width opening (i.e. 36" door with standard hinge)	<input type="checkbox"/>	<input type="checkbox"/>	
At least 18" clear floor area on latch, pull side of door	<input type="checkbox"/>	<input type="checkbox"/>	
Door handle no higher than 48" and operable with a closed fist	<input type="checkbox"/>	<input type="checkbox"/>	
Vestibule is 4 ft plus the width of the door swinging into the space	<input type="checkbox"/>	<input type="checkbox"/>	
Entrance(s) on a level that makes elevators accessible	<input type="checkbox"/>	<input type="checkbox"/>	
Door mats less than 1/2" thick are securely fastened	<input type="checkbox"/>	<input type="checkbox"/>	
Door mats more than 1/2" thick are recessed	<input type="checkbox"/>	<input type="checkbox"/>	
Grates in path of travel have openings of 1/2" maximum	<input type="checkbox"/>	<input type="checkbox"/>	
Signs at non-accessible entrance(s) indicate direction to accessible entrance	<input type="checkbox"/>	<input type="checkbox"/>	
Emergency egress – alarms with flashing lights and audible signals, sufficiently lighted	<input type="checkbox"/>	<input type="checkbox"/>	

No Indoor facilities

STAIRS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
No open risers	<input type="checkbox"/>	<input type="checkbox"/>	
Nosings not projecting	<input type="checkbox"/>	<input type="checkbox"/>	
Treads no less than 11" wide	<input type="checkbox"/>	<input type="checkbox"/>	
Handrails on both sides	<input type="checkbox"/>	<input type="checkbox"/>	
Handrails 34"-38" above tread	<input type="checkbox"/>	<input type="checkbox"/>	
Handrail extends a minimum of 1 ft beyond top and bottom riser (if no safety hazard and space permits)	<input type="checkbox"/>	<input type="checkbox"/>	No Stain
Handgrip oval or round	<input type="checkbox"/>	<input type="checkbox"/>	
Handgrip has a smooth surface	<input type="checkbox"/>	<input type="checkbox"/>	
Handgrip diameter between 1¼" and 1½"	<input type="checkbox"/>	<input type="checkbox"/>	
1½" clearance between wall and handrail	<input type="checkbox"/>	<input type="checkbox"/>	

DOORS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Minimum 32" clear opening	<input type="checkbox"/>	<input type="checkbox"/>	
At least 18" clear floor space on pull side of door	<input type="checkbox"/>	<input type="checkbox"/>	
Closing speed minimum 3 seconds to within 3" of the latch	<input type="checkbox"/>	<input type="checkbox"/>	
Maximum pressure 5 pounds interior doors	<input type="checkbox"/>	<input type="checkbox"/>	
Threshold maximum ½" high, beveled on both sides	<input type="checkbox"/>	<input type="checkbox"/>	No Indoor Facilities
Hardware operable with a closed fist (no conventional doorknobs or thumb latch devices)	<input type="checkbox"/>	<input type="checkbox"/>	
Hardware minimum 36", maximum 48" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
Clear, level floor space extends out 5 ft from both sides of the door	<input type="checkbox"/>	<input type="checkbox"/>	
Door adjacent to revolving door is accessible and unlocked	<input type="checkbox"/>	<input type="checkbox"/>	
Doors opening into hazardous area have hardware that is knurled or roughened	<input type="checkbox"/>	<input type="checkbox"/>	

RESTROOMS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
5 ft turning space measured 12" from the floor	<input type="checkbox"/>	<input type="checkbox"/>	ADA PortaJohn Only
AT LEAST ONE SINK			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Clear floor space of 30" by 48" to allow a forward approach	<input type="checkbox"/>	<input type="checkbox"/>	
Mounted without pedestal or legs, height 34" to top of rim	<input type="checkbox"/>	<input type="checkbox"/>	
Extends at least 22" from the wall	<input type="checkbox"/>	<input type="checkbox"/>	
Open knee space a minimum 19" deep, 30" width, and 27" high	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Cover exposed pipes with insulation	<input type="checkbox"/>	<input type="checkbox"/>	
Faucets operable with closed fist (lever or spring activated handle)	<input type="checkbox"/>	<input type="checkbox"/>	
AT LEAST ONE STALL			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Accessible to person using wheelchair at 60" wide by 72" deep	<input type="checkbox"/>	<input type="checkbox"/>	
Stall door is 36" wide	<input type="checkbox"/>	<input type="checkbox"/>	
Stall door swings out	<input type="checkbox"/>	<input type="checkbox"/>	
Stall door is self closing	<input type="checkbox"/>	<input type="checkbox"/>	
Stall door has a pull latch	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Lock on stall door is operable with a closed fist, and 32" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
Coat hook is 54" high	<input type="checkbox"/>	<input type="checkbox"/>	
TOILET			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
18" from center to nearest side wall	<input type="checkbox"/>	<input type="checkbox"/>	
42" minimum clear space from center to farthest wall or fixture	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Top of seat 17"-19" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
GRAB BARS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
On back and side wall closest to toilet	<input type="checkbox"/>	<input type="checkbox"/>	
1 1/4" diameter	<input type="checkbox"/>	<input type="checkbox"/>	
1 1/2" clearance to wall	<input type="checkbox"/>	<input type="checkbox"/>	
Located 30" above and parallel to the floor	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Acid-etched or roughened grab bar surface	<input type="checkbox"/>	<input type="checkbox"/>	
42" long grab bars	<input type="checkbox"/>	<input type="checkbox"/>	

RESTROOMS			
FIXTURES			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Toilet paper dispenser is 24" above floor	<input type="checkbox"/>	<input type="checkbox"/>	N/A
One mirror set a maximum 38" to bottom (if tilted, 42")	<input type="checkbox"/>	<input type="checkbox"/>	
Dispensers (towel, soap, etc.) at least one of each a maximum 42" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	

FLOORS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Non-slip surface	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Carpeting is high-density, low pile, non-absorbent, stretched taut, securely anchored	<input type="checkbox"/>	<input type="checkbox"/>	
Corridor width minimum is 3 ft	<input type="checkbox"/>	<input type="checkbox"/>	
Objects (signs, ceiling lights, fixtures) can only protrude 4" into the path of travel from a height of 27" to 80" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	

DRINKING FOUNTAINS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Spouts no higher than 36" from floor to outlet	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Hand operated push button or level controls	<input type="checkbox"/>	<input type="checkbox"/>	
Spouts located near front with stream of water as parallel to front as possible	<input type="checkbox"/>	<input type="checkbox"/>	
If recessed, recess a minimum 30" width, and no deeper than depth of fountain	<input type="checkbox"/>	<input type="checkbox"/>	
If no clear knee space underneath, clear floor space 30" x 48" to allow parallel approach	<input type="checkbox"/>	<input type="checkbox"/>	

TELEPHONES			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Highest operating part a maximum 54" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Access within 12" of phone, 30" high by 30" wide	<input type="checkbox"/>	<input type="checkbox"/>	
Adjustable volume control on headset so identified	<input type="checkbox"/>	<input type="checkbox"/>	

SIGNALS, OUTLETS, AND SWITCHES			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Switches and controls for light, heat, ventilation, windows, fire alarms, thermostats, etc., must be a minimum of 36" and a maximum of 48" above the floor for a forward reach, a maximum of 54" for a side reach	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Electrical outlets centered no lower than 18" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
Warning signals must be visual as well as audible	<input type="checkbox"/>	<input type="checkbox"/>	

SIGNS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Mounting height must be 60" to centerline of the sign	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Within 18" of door jamb or recessed	<input type="checkbox"/>	<input type="checkbox"/>	
Letters and numbers at least 1¼" high	<input type="checkbox"/>	<input type="checkbox"/>	
Letters and numbers raised .03"	<input type="checkbox"/>	<input type="checkbox"/>	
Letters and numbers contrast with the background color	<input type="checkbox"/>	<input type="checkbox"/>	

SWIMMING POOLS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Ramp at least 34" wide with a non-slip surface extending into the shallow end, slope not exceeding 1:6 with handrails on both sides	<input type="checkbox"/>	<input type="checkbox"/>	<i>Note: Pools may accommodate either ramp or lifting access.</i>
Lifting device	<input type="checkbox"/>	<input type="checkbox"/>	<i>Note: Pools may accommodate either ramp or lifting access.</i>
Transfer area 18" above the path of travel and a minimum of 18" wide	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Unobstructed path of travel not less than 48" wide around pool	<input type="checkbox"/>	<input type="checkbox"/>	
Non-slip surface	<input type="checkbox"/>	<input type="checkbox"/>	

SHOWER ROOMS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Stalls 36" by 60" minimum, with a 36" door opening	<input type="checkbox"/>	<input type="checkbox"/>	<i>Note: Showers must accommodate both wheel-in and transfer use</i>
Floors are pitched to drain the stall at the corner farthest from entrance	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Floors are non-slip surface	<input type="checkbox"/>	<input type="checkbox"/>	
Controls operate by a single lever with a pressure balance mixing valve	<input type="checkbox"/>	<input type="checkbox"/>	

Controls are located on the center wall adjacent to the hinged seat	<input type="checkbox"/>	<input type="checkbox"/>	
Shower heads attached to a flexible metal hose	<input type="checkbox"/>	<input type="checkbox"/>	
Shower heads attached to wall mounting adjustable from 42" to 72" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
Seat is hinged and padded and at least 16" deep, folds upward, securely attached to side wall, height is 18" to the top of the seat, and at least 24" long	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Soap trays without handhold features unless they can support 250 pounds	<input type="checkbox"/>	<input type="checkbox"/>	
2 grab bars are provided, one 30" and one 48" long, or one continuous L shaped bar	<input type="checkbox"/>	<input type="checkbox"/>	
Grab bars are placed horizontally at 36" above the floor line	<input type="checkbox"/>	<input type="checkbox"/>	

PICNICKING			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
A minimum of 5% of the total tables must be accessible with clear space under the tabletop not less than 30" wide and 19" deep per seating space and not less than 27" clear from the ground to the underside of the table. An additional 29" clear space (totaling 48") must extend beyond the 19" clear space under the table to provide access	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
For tables without toe clearance, the knee space under the table must be at least 28" high, 30" wide and 24" deep.	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Top of table no higher than 32" above ground	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Surface of the clear ground space under and around the table must be stable, firm and slip-resistant, and evenly graded with a maximum slope of 2% in all directions	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Accessible tables, grills and fire rings must have clear ground space of at least 36" around the perimeter	<input type="checkbox"/>	<input type="checkbox"/>	N/A

ADA FACILITY INVENTORY

LOCATION: *Columbia Field*

ACTIVITY	EQUIPMENT	NOTES
Picnic Facilities	Tables & Benches	<input type="checkbox"/> Located adjacent to accessible paths
		<input type="checkbox"/> Access to Open Spaces
		<input type="checkbox"/> Back and Arm Rests
		<input type="checkbox"/> Adequate number
	Grills	<input type="checkbox"/> Height of Cooking Surface
		<input type="checkbox"/> Located adjacent to accessible paths
	Trash Cans	<input checked="" type="checkbox"/> Located adjacent to accessible paths
	Picnic Shelters	<input type="checkbox"/> Located adjacent to accessible paths
<input type="checkbox"/> Located near accessible infrastructure and amenities		
Trails		<input type="checkbox"/> Surface material
		<input type="checkbox"/> Dimensions
		<input type="checkbox"/> Rails
		<input type="checkbox"/> Accessible signage
Swimming Facilities	Pools	<input type="checkbox"/> Entrance
		<input type="checkbox"/> Location from accessible parking
		<input type="checkbox"/> Safety features
	Beaches	<input type="checkbox"/> Location from accessible path into water
		<input type="checkbox"/> Handrails
		<input type="checkbox"/> Location from accessible parking
Play Areas	Play Equipment	<input type="checkbox"/> Same experience provided to all
	Access Routes	<input type="checkbox"/> Located adjacent to accessible paths
		<input type="checkbox"/> Enough space between equipment for wheelchair
Game Areas	Access Routes	<input checked="" type="checkbox"/> Located adjacent to accessible paths
		<input checked="" type="checkbox"/> Berm cuts onto courts
	Equipment	<input checked="" type="checkbox"/> Height
		<input checked="" type="checkbox"/> Dimensions
		<input checked="" type="checkbox"/> Spectator Seating

Boat Docks	Access Routes	<input type="checkbox"/> Located adjacent to accessible paths	N/A
		<input type="checkbox"/> Handrails	
Fishing Facilities	Access Routes	<input type="checkbox"/> Located adjacent to accessible paths	N/A
		<input type="checkbox"/> Handrails	
	Equipment	<input type="checkbox"/> Arm Rests	
		<input type="checkbox"/> Bait Shelves	
		<input type="checkbox"/> Fish Cleaning Tables	
Programming	<input type="checkbox"/> Learn-to-Swim	N/A	
	<input type="checkbox"/> Guided Hikes		
	<input type="checkbox"/> Interpretive Programs		
Services	<input type="checkbox"/> Information available in alternative formats	N/A	
	<input type="checkbox"/> Process to request interpretive services		

PARKING			
TOTAL SPACES		REQUIRED ACCESSIBLE SPACES	
Up to 25	<input type="checkbox"/>	1 space	
26-50	<input checked="" type="checkbox"/>	2 spaces	
51-75	<input type="checkbox"/>	3 spaces	
76-100	<input type="checkbox"/>	4 spaces	
101-150	<input type="checkbox"/>	5 spaces	
151-200	<input type="checkbox"/>	6 spaces	
201-300	<input type="checkbox"/>	7 spaces	
301-400	<input type="checkbox"/>	8 spaces	
401-500	<input type="checkbox"/>	9 spaces	
ACCESSIBLE SPACE SPECIFICATIONS	YES	NO	COMMENTS/TRANSITION NOTES
Accessible space located closest to accessible entrance	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Where spaces cannot be located within 200 ft of accessible entrance, drop-off area is provided within 100 ft.	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Minimum width of 13 ft includes 8 ft space plus 5 ft access aisle	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Van space – minimum of 1 van space for every accessible space, 8 ft wide plus 8 ft aisle. Alternative is to make all accessible spaces 11 ft wide with 5 ft aisle.	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Sign with international symbol of accessibility at each space or pair of spaces	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Sign minimum 5 ft, maximum 8 ft to top of sign	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Surface evenly paved or hard-packed (no cracks)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Surface slope less than 1:20, 5%	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Curbcut to pathway from parking lot at each space or pair of spaces, if sidewalk (curb) is present	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Curbcut is a minimum width of 3 ft, excluding sloped sides, has sloped sides, all slopes not to exceed 1:12, and textured or painted yellow	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

RAMPS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Slope Maximum 1:12	<input type="checkbox"/>	<input type="checkbox"/>	
Minimum width 4 ft between handrails	<input type="checkbox"/>	<input type="checkbox"/>	
Handrails on both sides if ramp is longer than 6 ft	<input type="checkbox"/>	<input type="checkbox"/>	
Handrails at 34" and 19" from ramp surface	<input type="checkbox"/>	<input type="checkbox"/>	
Handrails extend 12" beyond top and bottom	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Handgrip oval or round	<input type="checkbox"/>	<input type="checkbox"/>	
Handgrip smooth surface	<input type="checkbox"/>	<input type="checkbox"/>	
Handgrip diameter between 1¼" and 2"	<input type="checkbox"/>	<input type="checkbox"/>	
Clearance of 1½" between wall and wall rail	<input type="checkbox"/>	<input type="checkbox"/>	
Non-slip surface	<input type="checkbox"/>	<input type="checkbox"/>	
Level platforms (4ft x 4 ft) at every 30 ft, at top, at bottom, at change of direction	<input type="checkbox"/>	<input type="checkbox"/>	

SITE ACCESS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Accessible path of travel from passenger disembarking area and parking area to accessible entrance	<input type="checkbox"/>	<input type="checkbox"/>	
Disembarking area at accessible entrance	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Surface evenly paved or hard-packed	<input type="checkbox"/>	<input type="checkbox"/>	
No ponding of water	<input type="checkbox"/>	<input type="checkbox"/>	

PATH OF TRAVEL			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Path does not require the use of stairs	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Path is stable, firm and slip resistant	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
3 ft wide minimum	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Slope maximum 1:20 (5%) and maximum cross pitch is 2% (1:50).	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Continuous common surface, no changes in level greater than ½ inch	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Any objects protruding onto the pathway must be detected by a person with a visual disability using a cane	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

PATH OF TRAVEL			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Objects protruding more than 4" from the wall must be within 27" of the ground, or higher than 80"	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Curb on the pathway must have curb cuts at drives, parking and drop-offs	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

ENTRANCES			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Primary public entrances accessible to person using wheelchair, must be signed, gotten to independently, and <i>not</i> be the service entrance	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Level space extending 5 ft. from the door, interior and exterior of entrance doors	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Minimum 32" clear width opening (i.e. 36" door with standard hinge)	<input type="checkbox"/>	<input type="checkbox"/>	no
At least 18" clear floor area on latch, pull side of door	<input type="checkbox"/>	<input type="checkbox"/>	indoor
Door handle no higher than 48" and operable with a closed fist	<input type="checkbox"/>	<input type="checkbox"/>	
Vestibule is 4 ft plus the width of the door swinging into the space	<input type="checkbox"/>	<input type="checkbox"/>	
Entrance(s) on a level that makes elevators accessible	<input type="checkbox"/>	<input type="checkbox"/>	facility
Door mats less than 1/2" thick are securely fastened	<input type="checkbox"/>	<input type="checkbox"/>	
Door mats more than 1/2" thick are recessed	<input type="checkbox"/>	<input type="checkbox"/>	
Grates in path of travel have openings of 1/2" maximum	<input type="checkbox"/>	<input type="checkbox"/>	
Signs at non-accessible entrance(s) indicate direction to accessible entrance	<input type="checkbox"/>	<input type="checkbox"/>	
Emergency egress – alarms with flashing lights and audible signals, sufficiently lighted	<input type="checkbox"/>	<input type="checkbox"/>	

STAIRS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
No open risers	<input type="checkbox"/>	<input type="checkbox"/>	
Nosings not projecting	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Treads no less than 11" wide	<input type="checkbox"/>	<input type="checkbox"/>	
Handrails on both sides	<input type="checkbox"/>	<input type="checkbox"/>	
Handrails 34"-38" above tread	<input type="checkbox"/>	<input type="checkbox"/>	no indoor
Handrail extends a minimum of 1 ft beyond top and bottom riser (if no safety hazard and space permits)	<input type="checkbox"/>	<input type="checkbox"/>	
Handgrip oval or round	<input type="checkbox"/>	<input type="checkbox"/>	
Handgrip has a smooth surface	<input type="checkbox"/>	<input type="checkbox"/>	
Handgrip diameter between 1¼" and 1½"	<input type="checkbox"/>	<input type="checkbox"/>	facility
1½" clearance between wall and handrail	<input type="checkbox"/>	<input type="checkbox"/>	

DOORS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Minimum 32" clear opening	<input type="checkbox"/>	<input type="checkbox"/>	
At least 18" clear floor space on pull side of door	<input type="checkbox"/>	<input type="checkbox"/>	
Closing speed minimum 3 seconds to within 3" of the latch	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Maximum pressure 5 pounds interior doors	<input type="checkbox"/>	<input type="checkbox"/>	
Threshold maximum ½" high, beveled on both sides	<input type="checkbox"/>	<input type="checkbox"/>	no indoor
Hardware operable with a closed fist (no conventional doorknobs or thumb latch devices)	<input type="checkbox"/>	<input type="checkbox"/>	
Hardware minimum 36", maximum 48" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
Clear, level floor space extends out 5 ft from both sides of the door	<input type="checkbox"/>	<input type="checkbox"/>	facility
Door adjacent to revolving door is accessible and unlocked	<input type="checkbox"/>	<input type="checkbox"/>	
Doors opening into hazardous area have hardware that is knurled or roughened	<input type="checkbox"/>	<input type="checkbox"/>	

RESTROOMS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
5 ft turning space measured 12" from the floor	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
AT LEAST ONE SINK			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Clear floor space of 30" by 48" to allow a forward approach	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Mounted without pedestal or legs, height 34" to top of rim	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Extends at least 22" from the wall	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Open knee space a minimum 19" deep, 30" width, and 27" high	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Cover exposed pipes with insulation	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Faucets operable with closed fist (lever or spring activated handle)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
AT LEAST ONE STALL			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Accessible to person using wheelchair at 60" wide by 72" deep	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Stall door is 36" wide	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Stall door swings out	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Stall door is self closing	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Stall door has a pull latch	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Lock on stall door is operable with a closed fist, and 32" above the floor	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Coat hook is 54" high	<input type="checkbox"/>	<input checked="" type="checkbox"/>	No Hook
TOILET			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
18" from center to nearest side wall	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
42" minimum clear space from center to farthest wall or fixture	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Top of seat 17"-19" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
GRAB BARS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
On back and side wall closest to toilet	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
1¼" diameter	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
1½" clearance to wall	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Located 30" above and parallel to the floor	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Acid-etched or roughened grab bar surface	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
42" long grab bars	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

RESTROOMS			
FIXTURES			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Toilet paper dispenser is 24" above floor	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
One mirror set a maximum 38" to bottom (if tilted, 42")	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Dispensers (towel, soap, etc.) at least one of each a maximum 42" above the floor	<input checked="" type="checkbox"/>	<input type="checkbox"/>	


FLOORS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Non-slip surface	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Carpeting is high-density, low pile, non-absorbent, stretched taut, securely anchored	<input type="checkbox"/>	<input type="checkbox"/>	NA
Corridor width minimum is 3 ft	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Objects (signs, ceiling lights, fixtures) can only protrude 4" into the path of travel from a height of 27" to 80" above the floor	<input checked="" type="checkbox"/>	<input type="checkbox"/>	


DRINKING FOUNTAINS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Spouts no higher than 36" from floor to outlet	<input type="checkbox"/>	<input type="checkbox"/>	
Hand operated push button or level controls	<input type="checkbox"/>	<input type="checkbox"/>	
Spouts located near front with stream of water as parallel to front as possible	<input type="checkbox"/>	<input type="checkbox"/>	N/A
If recessed, recess a minimum 30" width, and no deeper than depth of fountain	<input type="checkbox"/>	<input type="checkbox"/>	
If no clear knee space underneath, clear floor space 30" x 48" to allow parallel approach	<input type="checkbox"/>	<input type="checkbox"/>	


TELEPHONES			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Highest operating part a maximum 54" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
Access within 12" of phone, 30" high by 30" wide	<input type="checkbox"/>	<input type="checkbox"/>	
Adjustable volume control on headset so identified	<input type="checkbox"/>	<input type="checkbox"/>	


SIGNALS, OUTLETS, AND SWITCHES			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Switches and controls for light, heat, ventilation, windows, fire alarms, thermostats, etc., must be a minimum of 36" and a maximum of 48" above the floor for a forward reach, a maximum of 54" for a side reach	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Electrical outlets centered no lower than 18" above the floor	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Warning signals must be visual as well as audible	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

SIGNS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Mounting height must be 60" to centerline of the sign	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Within 18" of door jamb or recessed	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Letters and numbers at least 1/4" high	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Letters and numbers raised .03"	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Letters and numbers contrast with the background color	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

SWIMMING POOLS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Ramp at least 34" wide with a non-slip surface extending into the shallow end, slope not exceeding 1:6 with handrails on both sides	<input type="checkbox"/>	<input type="checkbox"/>	<i>Note: Pools may accommodate either ramp or lifting access.</i>
Lifting device	<input type="checkbox"/>	<input type="checkbox"/>	<i>Note: Pools may accommodate either ramp or lifting access.</i>
Transfer area 18" above the path of travel and a minimum of 18" wide	<input type="checkbox"/>	<input type="checkbox"/>	
Unobstructed path of travel not less than 48" wide around pool	<input type="checkbox"/>	<input type="checkbox"/>	
Non-slip surface	<input type="checkbox"/>	<input type="checkbox"/>	

SHOWER ROOMS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Stalls 36" by 60" minimum, with a 36" door opening	<input type="checkbox"/>	<input type="checkbox"/>	<i>Note: Showers must accommodate both wheel-in and transfer use</i>
Floors are pitched to drain the stall at the corner farthest from entrance	<input type="checkbox"/>	<input type="checkbox"/>	
Floors are non-slip surface	<input type="checkbox"/>	<input type="checkbox"/>	
Controls operate by a single lever with a pressure balance mixing valve	<input type="checkbox"/>	<input type="checkbox"/>	

Controls are located on the center wall adjacent to the hinged seat	<input type="checkbox"/>	<input type="checkbox"/>	
Shower heads attached to a flexible metal hose	<input type="checkbox"/>	<input type="checkbox"/>	
Shower heads attached to wall mounting adjustable from 42" to 72" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
Seat is hinged and padded and at least 16" deep, folds upward, securely attached to side wall, height is 18" to the top of the seat, and at least 24" long	<input type="checkbox"/>	<input type="checkbox"/>	
Soap trays without handhold features unless they can support 250 pounds	<input type="checkbox"/>	<input type="checkbox"/>	
2 grab bars are provided, one 30" and one 48" long, or one continuous L shaped bar	<input type="checkbox"/>	<input type="checkbox"/>	
Grab bars are placed horizontally at 36" above the floor line	<input type="checkbox"/>	<input type="checkbox"/>	

PICNICKING			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
A minimum of 5% of the total tables must be accessible with clear space under the tabletop not less than 30" wide and 19" deep per seating space and not less than 27" clear from the ground to the underside of the table. An additional 29" clear space (totaling 48") must extend beyond the 19" clear space under the table to provide access	<input type="checkbox"/>	<input type="checkbox"/>	
For tables without toe clearance, the knee space under the table must be at least 28" high, 30" wide and 24" deep.	<input type="checkbox"/>	<input type="checkbox"/>	
Top of table no higher than 32" above ground	<input type="checkbox"/>	<input type="checkbox"/>	
Surface of the clear ground space under and around the table must be stable, firm and slip-resistant, and evenly graded with a maximum slope of 2% in all directions	<input type="checkbox"/>	<input type="checkbox"/>	
Accessible tables, grills and fire rings must have clear ground space of at least 36" around the perimeter	<input type="checkbox"/>	<input type="checkbox"/>	

ADA FACILITY INVENTORY

LOCATION: *LeStage / Coddings Skating Pond*

ACTIVITY	EQUIPMENT	NOTES	
Picnic Facilities	Tables & Benches	<input checked="" type="checkbox"/> Located adjacent to accessible paths	
		<input checked="" type="checkbox"/> Access to Open Spaces	
		<input type="checkbox"/> Back and Arm Rests	
		<input checked="" type="checkbox"/> Adequate number	
	Grills	<input type="checkbox"/> Height of Cooking Surface	N/A
		<input type="checkbox"/> Located adjacent to accessible paths	N/A
Trash Cans	<input checked="" type="checkbox"/> Located adjacent to accessible paths		
Picnic Shelters	<input type="checkbox"/> Located adjacent to accessible paths	N/A	
	<input type="checkbox"/> Located near accessible infrastructure and amenities	N/A	
Trails		<input checked="" type="checkbox"/> Surface material	
		<input checked="" type="checkbox"/> Dimensions	
		<input type="checkbox"/> Rails	
		<input type="checkbox"/> Accessible signage	
Swimming Facilities	Pools	<input type="checkbox"/> Entrance	
		<input type="checkbox"/> Location from accessible parking	N/A
		<input type="checkbox"/> Safety features	N/A
	Beaches	<input type="checkbox"/> Location from accessible path into water	
		<input type="checkbox"/> Handrails	
		<input type="checkbox"/> Location from accessible parking	N/A
	<input type="checkbox"/> Shade provided		
Play Areas	Play Equipment	<input type="checkbox"/> Same experience provided to all	
	Access Routes	<input type="checkbox"/> Located adjacent to accessible paths	N/A
		<input type="checkbox"/> Enough space between equipment for wheelchair	N/A
Game Areas	Access Routes	<input checked="" type="checkbox"/> Located adjacent to accessible paths	
		<input type="checkbox"/> ...n cuts onto courts	
	Equipment	<input type="checkbox"/> Height	
		<input type="checkbox"/> Dimensions	
	<input type="checkbox"/> Spectator Seating		

Boat Docks	Access Routes	<input type="checkbox"/> Located adjacent to accessible paths	N/A
		<input type="checkbox"/> Handrails	
Fishing Facilities	Access Routes	<input type="checkbox"/> Located adjacent to accessible paths	N/A
		<input type="checkbox"/> Handrails	
	Equipment	<input type="checkbox"/> Arm Rests	
		<input type="checkbox"/> Bait Shelves	
		<input type="checkbox"/> Fish Cleaning Tables	
Programming	<input type="checkbox"/> Learn-to-Swim		
	<input type="checkbox"/> Guided Hikes		
	<input type="checkbox"/> Interpretive Programs		
Services	<input type="checkbox"/> Information available in alternative formats		
	<input type="checkbox"/> Process to request interpretive services		

PARKING			
TOTAL SPACES		REQUIRED ACCESSIBLE SPACES	
Up to 25	<input type="checkbox"/>	1 space	
26-50	<input type="checkbox"/>	2 spaces	
51-75	<input checked="" type="checkbox"/>	3 spaces	
76-100	<input type="checkbox"/>	4 spaces	
101-150	<input type="checkbox"/>	5 spaces	
151-200	<input type="checkbox"/>	6 spaces	
201-300	<input type="checkbox"/>	7 spaces	
301-400	<input type="checkbox"/>	8 spaces	
401-500	<input type="checkbox"/>	9 spaces	
ACCESSIBLE SPACE SPECIFICATIONS	YES	NO	COMMENTS/TRANSITION NOTES
Accessible space located closest to accessible entrance	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Where spaces cannot be located within 200 ft of accessible entrance, drop-off area is provided within 100 ft.	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Minimum width of 13 ft includes 8 ft space plus 5 ft access aisle	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Van space – minimum of 1 van space for every accessible space, 8 ft wide plus 8 ft aisle. Alternative is to make all accessible spaces 11 ft wide with 5 ft aisle.	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Sign with international symbol of accessibility at each space or pair of spaces	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Sign minimum 5 ft, maximum 8 ft to top of sign	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Surface evenly paved or hard-packed (no cracks)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Surface slope less than 1:20, 5%	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Curbside to pathway from parking lot at each space or pair of spaces, if sidewalk (curb) is present	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Curbside is a minimum width of 3 ft, excluding sloped sides, has sloped sides, all slopes not to exceed 1:12, and textured or painted yellow	<input type="checkbox"/>	<input checked="" type="checkbox"/>	all open

RAMPS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Slope Maximum 1:12	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Minimum width 4 ft between handrails	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Handrails on both sides if ramp is longer than 6 ft	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Handrails at 34" and 19" from ramp surface	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Handrails extend 12" beyond top and bottom	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Handgrip oval or round	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Handgrip smooth surface	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Handgrip diameter between 1¼" and 2"	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Clearance of 1½" between wall and wall rail	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Non-slip surface	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Level platforms (4ft x 4 ft) at every 30 ft, at top, at bottom, at change of direction	<input type="checkbox"/>	<input checked="" type="checkbox"/>	

SITE ACCESS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Accessible path of travel from passenger disembarking area and parking area to accessible entrance	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Disembarking area at accessible entrance	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Surface evenly paved or hard-packed	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
No ponding of water	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

PATH OF TRAVEL			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Path does not require the use of stairs	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Path is stable, firm and slip resistant	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
3 ft wide minimum	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Slope maximum 1:20 (5%) and maximum cross pitch is 2% (1:50).	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Continuous common surface, no changes in level greater than ½ inch	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Any objects protruding onto the pathway must be detected by a person with a visual disability using a cane	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

PATH OF TRAVEL			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Objects protruding more than 4" from the wall must be within 27" of the ground, or higher than 80"	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Curb on the pathway must have curb cuts at drives, parking and drop-offs	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

ENTRANCES			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Primary public entrances accessible to person using wheelchair, must be signed, gotten to independently, and <i>not</i> be the service entrance	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Level space extending 5 ft. from the door, interior and exterior of entrance doors	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	N/A no indoor facilities
Minimum 32" clear width opening (i.e. 36" door with standard hinge)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
At least 18" clear floor area on latch, pull side of door	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Door handle no higher than 48" and operable with a closed fist	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Vestibule is 4 ft plus the width of the door swinging into the space	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Entrance(s) on a level that makes elevators accessible	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Door mats less than 1/2" thick are securely fastened	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Door mats more than 1/2" thick are recessed	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Grates in path of travel have openings of 1/2" maximum	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Signs at non-accessible entrance(s) indicate direction to accessible entrance	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Emergency egress – alarms with flashing lights and audible signals, sufficiently lighted	<input type="checkbox"/>	<input checked="" type="checkbox"/>	

STAIRS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
No open risers	<input type="checkbox"/>	<input type="checkbox"/>	<i>No Stairs</i>
Nosings not projecting	<input type="checkbox"/>	<input type="checkbox"/>	
Treads no less than 11" wide	<input type="checkbox"/>	<input type="checkbox"/>	
Handrails on both sides	<input type="checkbox"/>	<input type="checkbox"/>	
Handrails 34"-38" above tread	<input type="checkbox"/>	<input type="checkbox"/>	<i>N/A</i>
Handrail extends a minimum of 1 ft beyond top and bottom riser (if no safety hazard and space permits)	<input type="checkbox"/>	<input type="checkbox"/>	
Handgrip oval or round	<input type="checkbox"/>	<input type="checkbox"/>	
Handgrip has a smooth surface	<input type="checkbox"/>	<input type="checkbox"/>	
Handgrip diameter between 1¼" and 1½"	<input type="checkbox"/>	<input type="checkbox"/>	
1½" clearance between wall and handrail	<input type="checkbox"/>	<input type="checkbox"/>	

DOORS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Minimum 32" clear opening	<input type="checkbox"/>	<input type="checkbox"/>	<i>No doors</i>
At least 18" clear floor space on pull side of door	<input type="checkbox"/>	<input type="checkbox"/>	
Closing speed minimum 3 seconds to within 3" of the latch	<input type="checkbox"/>	<input type="checkbox"/>	
Maximum pressure 5 pounds interior doors	<input type="checkbox"/>	<input type="checkbox"/>	
Threshold maximum ½" high, beveled on both sides	<input type="checkbox"/>	<input type="checkbox"/>	
Hardware operable with a closed fist (no conventional doorknobs or thumb latch devices)	<input type="checkbox"/>	<input type="checkbox"/>	
Hardware minimum 36", maximum 48" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
Clear, level floor space extends out 5 ft from both sides of the door	<input type="checkbox"/>	<input type="checkbox"/>	
Door adjacent to revolving door is accessible and unlocked	<input type="checkbox"/>	<input type="checkbox"/>	
Doors opening into hazardous area have hardware that is knurled or roughened	<input type="checkbox"/>	<input type="checkbox"/>	

RESTROOMS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
5 ft turning space measured 12" from the floor	<input type="checkbox"/>	<input checked="" type="checkbox"/>	ADA Portajohn
AT LEAST ONE SINK			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Clear floor space of 30" by 48" to allow a forward approach	<input type="checkbox"/>	<input type="checkbox"/>	
Mounted without pedestal or legs, height 34" to top of rim	<input type="checkbox"/>	<input type="checkbox"/>	ADA Portajohn
Extends at least 22" from the wall	<input type="checkbox"/>	<input type="checkbox"/>	
Open knee space a minimum 19" deep, 30" width, and 27" high	<input type="checkbox"/>	<input type="checkbox"/>	
Cover exposed pipes with insulation	<input type="checkbox"/>	<input type="checkbox"/>	
Faucets operable with closed fist (lever or spring activated handle)	<input type="checkbox"/>	<input type="checkbox"/>	
AT LEAST ONE STALL			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Accessible to person using wheelchair at 60" wide by 72" deep	<input type="checkbox"/>	<input type="checkbox"/>	
Stall door is 36" wide	<input type="checkbox"/>	<input type="checkbox"/>	
Stall door swings out	<input type="checkbox"/>	<input type="checkbox"/>	ADA Portajohn
Stall door is self closing	<input type="checkbox"/>	<input type="checkbox"/>	
Stall door has a pull latch	<input type="checkbox"/>	<input type="checkbox"/>	
Lock on stall door is operable with a closed fist, and 32" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
Coat hook is 54" high	<input type="checkbox"/>	<input type="checkbox"/>	
TOILET			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
18" from center to nearest side wall	<input type="checkbox"/>	<input type="checkbox"/>	
42" minimum clear space from center to farthest wall or fixture	<input type="checkbox"/>	<input type="checkbox"/>	ADA Portajohn
Top of seat 17"-19" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
GRAB BARS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
On back and side wall closest to toilet	<input type="checkbox"/>	<input type="checkbox"/>	
1½" diameter	<input type="checkbox"/>	<input type="checkbox"/>	
1½" clearance to wall	<input type="checkbox"/>	<input type="checkbox"/>	
Located 30" above and parallel to the floor	<input type="checkbox"/>	<input type="checkbox"/>	ADA Portajohn
Acid-etched or roughened grab bar surface	<input type="checkbox"/>	<input type="checkbox"/>	
42" long grab bars	<input type="checkbox"/>	<input type="checkbox"/>	

RESTROOMS			
FIXTURES			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Toilet paper dispenser is 24" above floor	<input type="checkbox"/>	<input type="checkbox"/>	ADA Portajohns
One mirror set a maximum 38" to bottom (if tilted, 42")	<input type="checkbox"/>	<input type="checkbox"/>	
Dispensers (towel, soap, etc.) at least one of each a maximum 42" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	

FLOORS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Non-slip surface	<input type="checkbox"/>	<input type="checkbox"/>	NO Indoor facilities
Carpeting is high-density, low pile, non-absorbent, stretched taut, securely anchored	<input type="checkbox"/>	<input type="checkbox"/>	
Corridor width minimum is 3 ft	<input type="checkbox"/>	<input type="checkbox"/>	
Objects (signs, ceiling lights, fixtures) can only protrude 4" into the path of travel from a height of 27" to 80" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	

DRINKING FOUNTAINS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Spouts no higher than 36" from floor to outlet	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Hand operated push button or level controls	<input type="checkbox"/>	<input type="checkbox"/>	
Spouts located near front with stream of water as parallel to front as possible	<input type="checkbox"/>	<input type="checkbox"/>	
If recessed, recess a minimum 30" width, and no deeper than depth of fountain	<input type="checkbox"/>	<input type="checkbox"/>	
If no clear knee space underneath, clear floor space 30" x 48" to allow parallel approach	<input type="checkbox"/>	<input type="checkbox"/>	

TELEPHONES			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Highest operating part a maximum 54" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Access within 12" of phone, 30" high by 30" wide	<input type="checkbox"/>	<input type="checkbox"/>	
Adjustable volume control on headset so identified	<input type="checkbox"/>	<input type="checkbox"/>	

SIGNALS, OUTLETS, AND SWITCHES			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Switches and controls for light, heat, ventilation, windows, fire alarms, thermostats, etc., must be a minimum of 36" and a maximum of 48" above the floor for a forward reach, a maximum of 54" for a side reach	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Electrical outlets centered no lower than 18" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
Warning signals must be visual as well as audible	<input type="checkbox"/>	<input type="checkbox"/>	

SIGNS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Mounting height must be 60" to centerline of the sign	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Within 18" of door jamb or recessed	<input type="checkbox"/>	<input type="checkbox"/>	
Letters and numbers at least 1 1/4" high	<input type="checkbox"/>	<input type="checkbox"/>	
Letters and numbers raised .03"	<input type="checkbox"/>	<input type="checkbox"/>	
Letters and numbers contrast with the background color	<input type="checkbox"/>	<input type="checkbox"/>	

SWIMMING POOLS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Ramp at least 34" wide with a non-slip surface extending into the shallow end, slope not exceeding 1:6 with handrails on both sides	<input type="checkbox"/>	<input type="checkbox"/>	<i>Note: Pools may accommodate either ramp or lifting access.</i>
Lifting device	<input type="checkbox"/>	<input type="checkbox"/>	<i>Note: Pools may accommodate either ramp or lifting access.</i>
Transfer area 18" above the path of travel and a minimum of 18" wide	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Unobstructed path of travel not less than 48" wide around pool	<input type="checkbox"/>	<input type="checkbox"/>	
Non-slip surface	<input type="checkbox"/>	<input type="checkbox"/>	

SHOWER ROOMS			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
Stalls 36" by 60" minimum, with a 36" door opening	<input type="checkbox"/>	<input type="checkbox"/>	<i>Note: Showers must accommodate both wheel-in and transfer use</i>
Floors are pitched to drain the stall at the corner farthest from entrance	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Floors are non-slip surface	<input type="checkbox"/>	<input type="checkbox"/>	
Controls operate by a single lever with a pressure balance mixing valve	<input type="checkbox"/>	<input type="checkbox"/>	

Controls are located on the center wall adjacent to the hinged seat	<input type="checkbox"/>	<input type="checkbox"/>	
Shower heads attached to a flexible metal hose	<input type="checkbox"/>	<input type="checkbox"/>	
Shower heads attached to wall mounting adjustable from 42" to 72" above the floor	<input type="checkbox"/>	<input type="checkbox"/>	
Seat is hinged and padded and at least 16" deep, folds upward, securely attached to side wall, height is 18" to the top of the seat, and at least 24" long	<input type="checkbox"/>	<input type="checkbox"/>	N/A
Soap trays without handhold features unless they can support 250 pounds	<input type="checkbox"/>	<input type="checkbox"/>	
2 grab bars are provided, one 30" and one 48" long, or one continuous L shaped bar	<input type="checkbox"/>	<input type="checkbox"/>	
Grab bars are placed horizontally at 36" above the floor line	<input type="checkbox"/>	<input type="checkbox"/>	

PICNICKING			
SPECIFICATION	YES	NO	COMMENTS/TRANSITION NOTES
A minimum of 5% of the total tables must be accessible with clear space under the tabletop not less than 30" wide and 19" deep per seating space and not less than 27" clear from the ground to the underside of the table. An additional 29" clear space (totaling 48") must extend beyond the 19" clear space under the table to provide access	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
For tables without toe clearance, the knee space under the table must be at least 28" high, 30" wide and 24" deep.	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Top of table no higher than 32" above ground	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Surface of the clear ground space under and around the table must be stable, firm and slip-resistant, and evenly graded with a maximum slope of 2% in all directions	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Accessible tables, grills and fire rings must have clear ground space of at least 36" around the perimeter	<input type="checkbox"/>	<input type="checkbox"/>	N/A