



**NOTES:**

1. INSTALL BINDER, CUT NEAT LINE 6" FROM CURB LINE AND REMOVE BASE AND GRAVEL. REPLACE WITH CEMENT CONCRETE
2. ANY DESIGNATED CEMENT CONCRETE THAT IS ACCEPTABLE UNDER SECTION M4 OF THE STANDARD MHD SPECIFICATIONS MAY BE USED. ALL TEST REQUIREMENTS ARE WAIVED. HOT MIX ASPHALT SHALL NOT BE USED AS A SUBSTITUTE.



TOWN OF NORTH ATTLEBOROUGH, MASSACHUSETTS  
DEPARTMENT OF PUBLIC WORKS

Date Last Updated:  
05/15/2023

VERTICAL GRANITE CURB DETAIL  
N.T.S.

Detail Number:  
H-1.1